




**AGENDA FOR 14TH (SPECIAL)
MEETING OF BUILDING &
WORKS COMMITTEE**

JUNE-17, 2010



**NATIONAL INSTITUTE OF TECHNOLOGY
KURUKSHETRA-136119**

AGENDA FOR 14TH(Spl.) MEETING OF BUILDING & WORKS COMMITTEE

VENUE : SENATE HALL
NATIONAL INSTITUTE OF
TECHNOLOGY
KURUKSHETRA

DAY : THURSDAY

DATE : 17.06.2010

TIME : 11.30 AM

**NATIONAL INSTITUTE OF TECHNOLOGY
KURUKSHETRA**

CONTENTS

ITEM NO.	DESCRIPTION	PAGES
14.1	To confirm the minutes of 13 th meeting of the Building & Works Committee held on 25.02.2010.	1-4
14.2	To report the action taken on the minutes of the 13 th meeting of the Building & Works Committee held on 25.02.2010.	5
14.3	To consider & approve the revised cost Estimate of Additional Girls Hostel (300 capacity) at NIT, Kurukshetra.	6-28
14.4	To consider & approve the revised cost estimate for the construction of MBA/MCA Block - a Two storey framed structure Building at NIT, Kurukshetra.	29-51
14.5	To consider & approve the item(s) of work for the construction of Extension Block of Guest House Building at NIT, Kurukshetra.	52-68
14.6	To consider and approve the rough cost estimate for installation 11KV Sub-Station for additional Girls Hostel (300 Capacity) at NIT, Kurukshetra.	69-75
14.7	To consider and approve the rough cost estimate of civil works for construction of room (Size- 22'x16' with RCC Roof Slab) to accommodate 11KV Sub-Station Equipments and main LT Panel for Additional Girls Hostel (300 Capacity) at NIT, Kurukshetra.	76-79

CONSTITUTION OF BUILDING & WORKS COMMITTEE

- | | | |
|----|---|-----------------|
| 1. | Dr. M.N. Bandyopadhyay,
Director,
National Institute of Technology,
Kurukshetra | Chairperson |
| 2. | Nominee of the MHRD
On the B & WC of the
Institute. | Member |
| 3. | Sh. Vijay Prakash Saha
Chief Technical Advisor,
MECON, Chandigarh,
(Safety, Environment, Energy and Management Consultant).
W-16, Green Park, New Delhi-110016 | Member |
| 4. | Dr. Krishna Gopal
Dean (Planning & Development)
National Institute of Technology,
Kurukshetra | Member |
| 5. | Er. Niranjan Singh,
Superintending Engineer (Civil),
Chandigarh Central Circle, CPWD,
Chandigarh | Member |
| 6. | Er. Vimal Kumar
Superintending Engineer (Electrical),
Chandigarh Electrical Central Circle, CPWD,
Chandigarh | Member |
| 7. | Dr. S.K. Sharma,
Dean (Estate, EM & Constn.),
National Institute of Technology,
Kurukshetra | Special Invitee |
| 8. | Dr. V.P Singh
Prof. In-charge (Estate & Construction),
National Institute of Technology,
Kurukshetra | Special Invitee |
| 9. | Prof. C.P Bansal
Prof. I/C (EM)
National Institute of Technology,
Kurukshetra | Special Invitee |

- | | | |
|-----|---|------------------|
| 10. | Er. P.K Aggarwal
Executive Engineer (Construction cell)
National Institute of Technology,
Kurukshetra | Special Invitee |
| 11. | Sh. D.K. Kaushik,
Assistant Engineer (Elect.),
National Institute of Technology,
Kurukshetra | Special Invitee |
| 12. | Sh. S.N. Kaushik,
Assistant Engineer (Civil),
National Institute of Technology,
Kurukshetra | Special Invitee |
| 13. | Sh. R.P.S Lohchab
Registrar,
National Institute of Technology,
Kurukshetra | Member-Secretary |

Item No. 14.1 To confirm the minutes of 13th meeting of the Building & Works Committee held on 25.02.2010.

The minutes of the 13th Meeting of Building & Works Committee held on 25.02.2010 were circulated amongst the members vide letter No. NIT/13th BWC/1727/1313 dated 27.02.2010. No comments were received from any member. Some comments were received from Er. Vimal Kumar, Member of B &WC vide letter No. CCEC-1/23[130]/412 dated 02.03.2010 (copy enclosed as Annexure-I from page-2 to 3). A detailed reply is enclosed as Annexure-II on page-4.

The minutes may be confirmed.

-15-



भारत सरकार
केन्द्रीय लोक निर्माण विभाग
अधिक्षण अभियन्ता(वैद्युत),
चण्डीगढ़ केन्द्रीय वैद्युत परिमण्डल-I, केलोर्गि, 1,
केन्द्रीय सदा, सेक्टर-9, चण्डीगढ़
दूरभाष एवं फैक्स संख्या : 0172-2742241, 2740413



GOVT OF INDIA
CENTRAL PUBLIC WORKS DEPARTMENT
Superintending Engineer(Elect),
Chandigarh Central Elect Circle-I, CPWD,
Kendriya Sadan, Sector-9, Chandigarh
Phone & FAX No . 0172-2742241;2740413

संख्या.No.CCEC-I/23[130] 412

दिनांक/Dated: 2, 03.2010

सेवा में,

✓ **Shri R.P.S. Lohchab**
Registrar and Member Secretary,
Building and Works Committee,
National Institute of Technology
Kurukshetra [Hr] - 136119.

Sub Building and Works Committee Meeting held on 25.02.2010.

Ref Your office letter No.NIT/13th BWC/1716/1106 dated 22.02.2010.

This refers to the Agenda Points discussed during the 13th Building and Works Meeting held at NIT Kurukshetra, on 25.02.2010. The following observations are brought to your notice for inclusion in the minutes of the meeting and necessary action, as required:-

[1] **Non-Preparation of the cost estimates and revised cost estimates based on Delhi Schedule of Rates and Plinth Area Rates approved by CPWD.**

During the last Building and Works Committee meeting, it had been impressed upon by the Members that all the estimates being put up to B&W Committee should be based on Delhi Schedule of Rates and the Plinth Area rates approved by CPWD. This, however, has not been followed so far and even now the estimates which were put up to the B&W Committee were based on Haryana P.A.R. It was emphasized that no further estimates will be entertained by the B&W Committee if these are not as per the CPWD Norms.

[2] **Tender details i.e the tenders received, tendered rates, justification etc.**

In the agenda items for the cost estimates/revised cost estimates, it is seen that as per the practice being followed, the cost estimates/revised cost estimates being put up to the Committee are justified with respect to the tendered cost and the rates of the lowest tenderer. The percentage above/below the justification are also put up to the Committee. It is felt that such details are not required to be considered by the Committee since the procedure related to call of tenders and its acceptance is beyond the purview of the the Committee. It may kindly be ensured that the cases being put up to the Committee are based on the cost estimates/revised cost estimates prepared by the Engineering Wing of NIT and no details pertaining to the rates of the tenders received, tenders called should be given therein.

[3] **Item No.11.3 of Agenda item No.13.2.**

The following amendments need to be made in the para 11.3 of agenda item No.13.2 i.e,

"[i]To consider and approve revised cost estimate for providing and installation of Electrical Sub Station HT/LT Distribution including street lighting and feeder pillars etc., non residential area at NIT Kurukshetra.

[ii]Providing and installation of electrical Sub Station, HT/LT Distribution and feeder pillars in residential area at NIT Kurukshetra.

The work pertaining to only non-residential portion amounting to Rs.578 lacs has been allocated to CPWD whereas in the paragraph, it is written that complete work pertaining to non-residential and residential area amounting to Rs.801.00 lacs has been allocated to CPWD. This needs to be corrected since as per A/A & E/S accorded for the work vide NIT Kurukshetra, letter No.CC/No/610/7167 dated 13.8.09, the sanction is for Rs.578 lakhs. It may kindly be seen that necessary action for finalization of the scheme and call of tenders is to be taken up by the Chief Engineer[e]NR, CPWD, New Delhi.

(विमल कुमार)

अधीक्षण अभियंता (वैद्युत)

चण्डीगढ केन्द्रीय वैद्युत परिमंडल No.1

Copy to

[1] अधीक्षण अभियंता, चण्डीगढ केन्द्रीय परिमंडल, के०ली०नि०वि०. चण्डीगढ

(विमल कुमार)

अधीक्षण अभियंता (वैद्युत)

चण्डीगढ केन्द्रीय वैद्युत परिमंडल No.1

NATIONAL INSTITUTE OF TECHNOLOGY
(INSTITUTION OF NATIONAL IMPORTANCE)
KURUKSHETRA

No/CC/905/1941

Dated: 31.03.2010

To,

Sh. Vimal Kumar,
Member B & WC, NIT, Kurukshetra - Cum -
Superintending Engineer (Elect.),
Central Public Works Department,
Chandigarh Central Elect Circle-I, CPWD,
Kendriya Sadar, Sector-9, Chandigarh.

Subject:- Building and Works Committee Meeting held on 25.02.2010.**Reference:- Your office letter No. CCEC-I/23[130]/412 Dated 02/03/2010.**

With reference to above letter, the pare wise reply to the observations raised by you is as under:-

(1) **Non- Preparation of the cost estimates and revised cost estimates based on Delhi Schedule of Rates and Plinth Area Rates approved by CPWD.**

- In the 12th Special meeting of B&WC held on 03.09.2009, the Hon'ble members desired & decided that the estimate of all the new works yet to be taken in hand should be framed on DSR & plinth area rates approved by CPWD & not on HSR basis.
- In the 13th meeting of B&WC held on 25.02.2010 all the works contained in the Agenda of B&WC meeting were old works which were already approved in the previous B&WC meetings & such estimates which were prepared earlier on HSR were again revised on latest approved rates of HSR.
- This observation of Hon'ble member has already included in the minutes of the meeting of 13th B&WC meeting that in future the estimates may be prepared on DSR basis in accordance with CPWD norms.

(2) **Tender details i.e. the tenders received, tendered rates, justification etc.**

In Principle, it was agreed in the 13th B&WC meeting and in future Agenda of meeting will be framed accordingly

(3) **Item No. 11.3 of Agenda item No. 13.2.**

Item will be corrected before placing in the ensuing meeting of B&WC.

It is for your kind information, please.

[Signature]
3/3/10
Prof. I/C (E & C)

✓ Copy to Registrar for kind information, please.

Discuss urgently
AK
31/3

Discussed
Comments read
+ reply given by
us may also
reported to the
B&WC in next
meeting
AK

N.I.T.		KURUKSHETRA	
Dy. No. 6536		Date 7/4/10	
R	DM	DA	DO
E	M	PC	CH
HI	CA	PG	PS
SE	PT	HS	ST

**Item No. 14.2 To report the action taken on the minutes of the
13th meeting of the Building & Works Committee
held on 25.02.2010.**

The action taken on the minutes of the 13th meeting of
the Building & Works Committee held on 25.02.2010 will be reported in
the next meeting of Building & Works Committee.

Item No. 14.3 To consider & approve the revised cost Estimate of Additional Girls Hostel (300 capacity) at NIT, Kurukshetra.

The B & WC in it's 10th meeting held on 19.02.2009 vide item no. 10. Approved a sum of Rs. 948.35 lac. for the construction of Additional Girls hostel (300 Capacity) at NIT, Kurukshetra.

The work of the above said building is under construction, during execution of this work some quantities have been increased because of final detailed architectural/structural drawings & design and in addition of construction of cycle stand & CC pavement and parking which were not included in the preliminary estimate.

As explained above the revised cost estimate amounting to Rs. 1072.33 lac. has been framed and duly scrutinized by the Construction Cell to cover the cost of additional items & quantities.

It is therefore requested that B & VC may kindly consider and approve the revised cost estimate amounting to Rs. 1072.33 lac. for the above cited work.

1

(B) ESTIMATION SHEET													
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)
(i)	30.70 a(i)	Soap dish large	132	Each	59.000	250%	206.50	27258.00	195.00	0.000	63.00	0	1300
12		Providing and fixing in position best Indian make bevelled edge 5.5mm thick mirror fixed in position by means of 4 nos. C.P. brass screws and washers complete including cutting and making good the walls etc.											
(a)		Indian make											
(i)	30.71	500mm x 450mm	68	Each	107.000	250%	374.50	25466.00	110.00	0.000	42.00	0	150
13		Providing and fixing in position best Indian make coat & hat hooks fixed with C.P. brass screws complete including cutting and making good the walls etc.					0.00					0	
(a)		C.P. Brass					0.00					0	
(ii)	30.73	Two way	624	Each	43.000	250%	150.50	93912.00	780.00	0.000	155.00	0	230
14		Providing and fixing in position super quality 65mm i/d opening C.P. brass dome type hinged grating weighting about 750 gms. Fixed in cement mortar 1:2 complete in all respects (as required by the Engineer-in-charge)	60	Each	67.500	250%	236.25	14175.00	60.00	0.000	0	0	
15		Providing & fixing in position 15mm i/d C.P. brass bib cocks of best quality (as required by the Engineer-in-charge)					0.00					0	
a)	30.75(a)	Bt cock long body	180	Each	116.000	250%	406.00	73080.00	240.00	0.000	60.00	0	20
c)	30.75(c)	Bt Cocks	82	Each	100.000	250%	350.00	28700.00	90.00	0.000	8.00	0	
16		Providing and fixing in position C.P. brass stop cocks (as approved by Engineer-in-charge)					0.00						
a)		15mm stop cocks					0.00						
ii)	30.76	Concealed stop cocks with flange	195	Each	130.000	250%	455.00	88725.00	195.00	0.000	0.00	0	
17		Providing and fixing in position best Indian make C.P. brass inlet connection 15mm with 375mm pipe & C.P. brass nuts.	468	Each	115.000	250%	402.50	188370.00	458.00	0.000	0.00	0	
18		Providing and fixing in position HCl soil, waste, vent pipes to ISI specification or any other reputed firm including cutting & wastage etc. & cutting holes in walls, roofs or floor etc. and making good the floor & wall but excluding cost of lead jointing					0.00						
(a)	30.84(a)	100mm internal dia	828	Mtr.	97.500	300%	390.00	322920.00	828.00	0.000	0.00	0	
(b)	30.84(b)	75mm internal dia	965	Mtr.	83.000	300%	332.00	320380.00	965.00	0.000	0.00	0	
19		Providing lead caulked joints to HCl pipes & specials conforming to ISI specification of ELC or any other reputed firm including cost of lead yarn, fuel & tools etc.					0.00						
a)	30.87	100mm internal dia(1.13 kg)	960	Each	33.500	250%	117.25	112560.00	960.00	0.000	0.00	0	
(b)	30.87	75mm internal dia(0.91 kg)	1080	Each	27.500	250%	96.25	103950.00	1080.00	0.000	0.00	0	

8

20	20	flat iron clamps made out of MS flat not less than 5mm of the approved design for fixing CI soil waste vent or anti pipes to walls complete in all respects including cutting and making good the walls and floor	192	Each	12.500	300%	0.00	9600.00	192.00	0.00	0.00	0
a)	30.88	For 100 mm internal dia pipes	192	Each	12.500	300%	0.00	9600.00	192.00	0.00	0.00	0
b)	30.88	For 75mm internal dia pipes	192	Each	11.000	300%	44.00	8448.00	192.00	0.00	0.00	0
21		Providing and fixing HCl floor trap ISI marked of the self cleaning design with C.P brass hinged grating with or without vent arm & including cement concrete 1:2:4 complete in all respects					0.00					0
(b)	30.89	With 75mm internal dia outlet	56	Each	105.000	300%	420.00	23520.00	56.00	0.00	0.00	0
22		Providing and fixing in position HCl 50mm internal diameter outlet plain nahani trap ISI marked of the self cleaning design with CP brass hinged grating with frame weighing 6.80 kg each fixed complete as fully described in item no. 30.89 above					0.00					0
b)	30.90	75mm i/d outlet plain Nahani Trap	168	Each	100.000	300%	490.00	67200.00	180.00	0.00	12.00	0
23		Providing and fixing in position HCl specials for soil waste vent pipes to ISI specification including cutting holes in walls & making good but excluding cost of lead joints					0.00					0
30.91							0.00					0
(a)		For 100mm internal dia pipes					0.00					0
(i)		Heal rest bend	27	Each	58.000	300%	232.00	6264.00	50.00	0.00	23.00	0
(iv)		Single junction with door 100mm x 100mm x 100mm	80	Each	86.500	300%	346.00	27680.00	80.00	0.00	0.00	0
vi)		Single junction plain 100mm x 100mm x 100mm	60	Each	76.500	300%	306.00	18360.00	60.00	0.00	0.00	0
xiii)		Bend with door	30	Each	60.000	300%	240.00	7200.00	30.00	0.00	0.00	0
(xiv)		Bend plain	30	Each	53.000	300%	212.00	6360.00	30.00	0.00	0.00	0
xvii)		door piece	30	Each	53.000	300%	212.00	6360.00	30.00	0.00	0.00	0
xvi)		Cowls	27	Each	36.500	300%	146.00	3942.00	27.00	0.00	0.00	0
xxii)		Collars	108	Each	27.500	300%	110.00	11880.00	108.00	0.00	0.00	0
b)		For 75mm internal dia pipes					0.00					0
i)		Heal rest bend	27	Each	39.500	300%	158.00	4266.00	27.00	0.00	0.00	0
(iv)		Single junction with door 75mm x 75mm x 75mm	80	Each	59.000	300%	236.00	18880.00	80.00	0.00	0.00	0
xiii)		Bend with door	30	Each	42.000	300%	168.00	5040.00	30.00	0.00	0.00	0
(xiv)		Bend plain	30	Each	39.500	300%	158.00	4740.00	30.00	0.00	0.00	0
(xvi)		door piece	30	Each	40.500	300%	162.00	4860.00	30.00	0.00	0.00	0
xvii)		Cowls	27	Each	28.000	300%	112.00	3024.00	27.00	0.00	0.00	0
xviii)		Collars	190	Each	22.500	300%	90.00	17100.00	190.00	0.00	0.00	0
24		Cutting chase in brick wall in cement for embedding G.I or HCl pipe lines & making good the same					0.00					0
a)	30.95	Size 75x75mm	288	Mtr.	6.000	250%	21.00	6048.00	288.00	0.00	0.00	0
25		Painting HCl soil waste and vent pipes and fittings with black bitumastic ordinary paint of approved manufacture two coats on new work.					0.00					0
30.101							0.00					0

ESTIMATE ON FORM 1988 PREPARED BY THE ENGINEER IN CHARGE									
Sl. No.	Particulars	Unit	Qty	Rate	Amount	30	30	30	30
a)	75mm internal dia	Mtr.	346	4.73	1634.85	240	346	0.00	0
b)	Providing and fixing in position automatic brass ball valves in tanks					1634.85	346.00	0.00	0
b)	With plastic ball			0.00				0.00	0
(iii)	25mm diameter			0.00				0.00	0
27	Providing and fixing in position Gully traps fixed in cement concrete 1:4:8 with HCl grating 150x150mm CI cover weighing approximately 7.26 kg & frame clear opening 300 x 300mm and chamber including cost of brick work 1:5 cement concrete 1:8:16 and CC 1:2	Each	29	229.25	6648.25		29.00	0.00	0
b)	100mm internal dia HCl gully traps.			0.00				0.00	0
30.114(b)		Each	36	832.00	29952.00		36.00	0.00	0
28	Providing and fixing in position best Indian make vitreous china ware channel of size 600mm x 150 including laying and fixing in cement concrete 1:2:4 complete as required by the Engineer-in-charge.								
30.115	White	Each	68	322.00	21896.00		68.00	0.00	0
29	Cutting holes upto 23cm through brick work in cement wall for pipes and making good								
28.24				0.00				0.00	0
a)	11.43cm thickness of walls	Each	300	44.10	13230.00		300.00	0.00	0
b)	22.86 cm thickness of walls	Each	420	64.10	26923.05		420.00	0.00	0
30	Bailing out water from the trenches for making new connections in fully charged pipelines								
28.47									
a)	Upto 200mm internal dia	Each	5	212.63	1063.13		5.00	0.00	0
31	Constructing brick masonry inspection chamber upto 60 mtr. Depth in cement mortar 1:5 cement concrete 1:2:4 benching, 12mm thick cement plaster, RCC 1:2:4 slab 100mm thick with 455 x 455mm x 455x610mm inside light duty GI inspection chamber cover & frame								
a)	Size 450x450mm inside	Each	0	1780.20	0.00		35.00	0.00	0
c)	Size 600x900mm inside	Each	60	2967.00	178020.00		30.00	30.000	89010
32	Extra for every 0.30mts. Depths to inspection chamber								
a)	450mmx450mm	Each	0	395.60	0.00		15.00	0.00	0
c)	600mm x 900mm	Each	60	597.70	35862.00		60.00	0.00	0
33	Excavation for pipelines running under pressure in trenches and pits in open areas where disposal of surplus earth is done along with the alignment and restoration of unmetalled surface to the original condition								
a)	Without timbering and shoring upto 1.5 meters depth	Cum	328	4120.00	13513.60		328.00	0.00	0

5/10

S.N.	Ref. HSR No.	Description	Qty.	Unit	Total Rate	Estimated	Total Rate	Qty. likely to executed	Qty. in Saving	Qty. in Excess	Saving Amount Rs.	Excess Amount Rs.
					(In Rs.)	Cost Rs.						
38		SUB PART - IV INTERNAL PH										
		Providing and fixing in position best Indian make (to the approval of Engineer-in-charge) 580mm white Indian make Onssa type water closet suit for sinking into floor with raised foot best treads with 100mm H.C.I trap along with -	55	Each	1500.00	196000.00	3200	55	0	0	0	0
	NS	White PVC 10 ltrs Capacity low level flushing cistern (as approved by Engineer-in-charge) complete with internal PVC fitting like suction, 15mm i/d ball cock along with R.S of CI painted bracket and 32mm dia CP/GI outlet pipes Mosquito proof over floor etc										
39		Providing and fixing in position best Indian make (to the approval of Engineer-in-charge) Single trap symphonic European type white water closet suit consisting of -	33	Each	4500.00	148500.00	3300	33	0	0	0	0
	(i)	White PVC 10 ltr. Capacity low level flushing like syption, 15mm i/d ball cock along with R.S or CI bracket and 32mm dia CP brass bend for out let. Mosquito proof over flow pipe etc										
	(ii)	Best laid in make white plastic seat (solid) and i/d fitting with set & C.P. chromium plated hinges and rubber buffers (to the approved of Engineer-in-charge) Complete in all respect including cutting and making good the wall and floor										
40		Providing and fixing in position C.P. jet connection of EWC complete including C.P. plate for jet & PVC connection for jet point complete in all respects	33	Each	300.00	9900.00	35	33	0	0	0	0
41	NS	Providing, laying, jointing glazed stoneware pipes grade A with stiff mixture of cement mortar in the proportion of 1:1 (1 cement, 1 fine sand) including testing of joints etc. complete										
	a)	150mm i/d	350	Mtr	150.00	144000.00	175	348	0	0	60000	0
	b)	200mm i/d	350	Mtr	230.00	82800.00	260	200	160	0	41600	0
42	NS	Providing and fixing of G.M. peat valves heavy patterns with hand wheels ISI marked to GI pipe lines.										
	a)	25mm i/d	72	Each	400.00	28800.00	450	72	0	0	0	0
	b)	40mm i/d	39	Each	850.00	33150.00	625	39	0	0	0	0
	c)	80mm i/d	8	Each	1600.00	12800.00	2100	12	0	4	0	8400
43	NS	Providing, testing and fixing G.I. pipe 'B' class medium duty including cost of specials such as Tee, elbow, bends etc. and threading inside the building & Ground										
		15mm i/d	2400	Mtr	120.00	288000.00	135	2400	0	0	0	0
		20mm i/d	35	Mtr	144.00	51840.00	150	360	0	0	0	0
		25mm i/d	1440	Mtr	190.00	273600.00	195	1440	0	0	0	0
		40mm i/d	960	Mtr	250.00	240000.00	270	960	0	0	0	0
		50mm i/d	420	Mtr	300.00	126000.00	350	420	0	0	0	0
		80mm i/d	600	Mtr	500.00	300000.00	550	600	0	0	0	0
46	NS	Extra for providing and fixing union coupling to G.I. pipe lines including cost of union complete									0	0
		15mm i/d	24	Each	50.00	1200.00	90	24	0	0	0	0
		20mm i/d	12	Each	78.00	936.00	120	12	0	0	0	0
		25mm i/d	30	Each	100.00	3000.00	170	30	0	0	0	0
		40mm i/d	12	Each	180.00	2160.00	320	12	0	0	0	0
		80mm i/d	24	Each	288.00	6912.00	750	24	0	0	0	0
		Providing and strutting S & S centrifugally cast (spun) iron pipes (Class LA) complete in trenches to the approval of Engineer-in-charge										
48	NS	80mm i/d	224	Mtr	925.00	207200.00	1250	300	0	75	0	95000
		Supplying and fixing ISI marked sluice valve double flanged with brass spindle complete in all respect to the approval of Engineer-in-charge, 80mm	6	Each	3000.00	18000.00	2000	6	0	0	0	0
	NS	Const. of sluice valve haudi 1m x 1m x 1m with brick work 1:5 cement sand mortar finished with 12.5 mm cement plaster 1:4 including R.C.C. 1:2:4 slab with reinforcement, surface box complete in all respect to the approval of Engineer-in-charge.	6	Each	3000.00	18000.00	3500	6	0	0	0	0

[illegible]

(BASED ON HSR-1988 & LATEST SANCTIONED PREMIUM W.E.F. 01-01-2008)												
S.No	Ref.	Description	Qty.	Unit	HSR Rate (In Rs.)	Estimated Cost Rs.	Total Rate	Qty likely to executed	Qty. in Saving	Qty. in Excess	Saving Amount Rs	Excess Amount Rs
		SUB PART-I: INTERNAL CIVIL WORKS (NON SCHEDULE ITEMS)										
15		Providing and fixing PVC rain water pipe, I.S.I. mark supreme make single socketed pipes including solvent solution 160mm diameter complete in all respect pressure 6kgm per cm2										
	N.S	160mm diameter pipe	576	Mtr.	800.00	460800.00	300.00	710.00	0.00	134.00	0.00	40200.00
16		Providing & fixing PVC door bend including solvent solution complete in all respect.										
	N.S	160 mm diameter pipe	320	Each	500.00	160000.00	200.00	80.00	240.00	0.00	43000.00	0.00
17		Providing & fixing PVC plain bends in position with solvent solution complete in all respect.										
	N.S	For 150mm diameter pipe	45	Each	400.00	18000.00	200.00	0.00	0.00	0.00	0.00	0.00
		The rate quoted by the contractor shall be for all heights and levels as per drawings and for all scaffolding work and other connecting operations for below mentioned items.										
59		Providing and fixing 18 mm thick mirror polished, machine cut for Kitchen plateforms, vanity counters facias and similar locations of required size of approved shade, colour and texture laid over 20 mm thick base cement mortar 1:3 with joints treated with (granite stone)										
a)	NS	Granite stone (Z-Black)	88	sqm	3000.00	264000.00	2600.00	160.00	0.00	72.00	0.00	187200.00
b)	NS	Cheema Pink Colour (1st quality)	800	sqm	2200.00	1760000.00	1500.00	680.00	120.00	0.00	180000.00	0.00
70		Extra for providing edge moulding to granite stone counters including machine polishing to edge to give high gloss finish etc.. Complete in all respects										
	NS		150	Mtr.	150.00	22500.00	100.00	700.00	0.00	550.00	0.00	5500.00
71		Providing and fixing first class plain coloured glazed tiles (of Orient/Somany make) of size 200x300 mm with minimum thickness 5mm in skirting and dado on 12mm thick cement plaster 1:3 (1 cement:3 coarse sanc) the back of the tiles to be buttered with grey cement slurry.										
	NS		2695	Sqm.	550.00	1482250.00	500.00	4300.00	0.00	1605.00	0.00	802500.00

54-

BASED ON T-1988 LATEST SANCTIONED PREMIUM W.T.F. 01/PJT-2008												
72		Providing and fixing 150mm wide sheet covering over expansion joints with rawl plugs and aluminium screws as per design to match the colour/shade of wall treatment with 3.15mm thick aluminium fluted strips.	200	Mtr.	330.00	66000.00	250.00	1100.00	0.00	900.00	0.00	225000.00
73	NS	Providing, laying & fixing including necessary screws 350mm wide 3.15 thick aluminium sheet bend to shape as per drawing/ instructions to act as metal cradle on expansion joint including embedding in concrete complete in all respects upto the entire satisfaction of the EIC	415	Mtr.	700.00	290500.00	100.00	415.00	0.00	0.00	0.00	0.00
74		Providing Dr. Fixit pidiseal PS 41G (Gun grade), 42P (Pouring grace) or equivalent for horizontal and vertical expansion joint complete in all respects as per manufacturer detail to the satisfaction of EIC on all the floors 50mm wide & 20mm deep	200	Mtr.	250.00	50000.00	800.00	200.00	0.00	0.00	0.00	0.00
75	NS	Providing expansion joints in roof slab, terrace joints filled with bitumen filler or impregnated fiber board etc. all complete as per building specifications and directions of the Engineer-in-charge.	1450	Mtr.	250.00	362500.00	25.00	1450.00	0.00	0.00	0.00	0.00
76		50mm wide & 20mm deep Providing precast CC jali 1:2:4 reinforced with 1:6 mm dia mild steel wire including centering & shuttering, roughening, cleaning, fixing and finishing in CM 1:3 etc. complete excluding plastering of the joints stills and soffits, 100 mm thick	260	Sqm.	1000.00	260000.00	500.00	460.00	0.00	200.00	0.00	100000.00
77	NS	Providing and fixing 25mm CP fencing rod in Cupboard complete with all necessary fittings.	270	Mtr.	150.00	40500.00	50.00	270.00	0.00	0.00	0.00	0.00
78	NS	Providing and laying 303mm dia NP -2 pipe complete with sockets as per satisfaction of the Engineer-in-charge	200	Mtr.	900.00	180000.00	450.00	300.00	0.00	100.00	0.00	45000.00
79	NS	Providing and fixing in position 50mm x50mm hollow sq. pipe for parapet railing or any type of railing including cost of welding roads etc. complete with one coat of primer.	2500	kg	80.00	200000.00	65.00	4500.00	0.00	2000.00	0.00	130000.00

(BASED ON TSK-1988 & LATEST SANCTIONED PREMIUM W.T.F. 01-07-2008) Providing and laying in floor Prem										
80										
	coloured matt finish ceramic tiles of Orient/Kajaria make, size 300mm x 300mm (thickness as per manufacture) without warpage, laid on 20mm thick cement mortar 1:3 (1 cement: 3 coarse sand) including grouting the join & pigment (first quality anti skid tiles to be used)	250	Sqm	600	156000.00	600	840.00	0.00	580.00	0.00
81	NS									348000
	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS : 1285, fixed with rawl plugs and (2mm thick)									
81.1	For fixed portion.									
81.1.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic									
NS		303	kg	290.45	88006.35	350	303.00	0.00	0.00	0.00
81.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for									
81.2.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)									
NS		540	kg	310.45	167643.00	350	540.00	0.00	0.00	0.00
82	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be p									
82.1	With float glass panes of 5.50 mm thickness	146	sqm	673.55	98338.30	550	146.00	0.00	0.00	0.00
83	Providing and fixing double action hydraulic floor spring of approved brand and manufacture IS : 6315 marked, for									
83.1	With stainless steel cover plate	17	each	1733.50	29469.50	1750.00	17.00	0.00	0.00	0.00

- 16 -

[illegible]

S.No	HSR No.	Description	Qty.	Unit	HSR Rate (in Rs.)	C.P	Total Rate	Estimated Cost	Qty. In Saving	Qty. In Excess	Saving Amount Rs.	Excess Amount
		SUB PART-1: INTERNAL CIVIL WORKS (SCHEDULE ITEMS)										
1	6.8	Earth work in excavation in foundation, trenches etc. in all kind of soils, not exceeding 2 mtrs. depth including dressing of bottom and sides of trenches, stacking of the excavated soil, clear from the edge of excavation and subsequent filling around mason	2000	100 Cum	1108.10	350%	4986.450	99729.000	0.00	3600.00	0.00	1795
2	6.27	Clearing grass and removal of the rubbish upto distance of 50m outside the periphery of the area cleared.	8350	100 sqm	21.45	300%	85.800	7164.300	0.00	1210.00	0.00	10
3	10.39	Cement concrete 1:4:8 with stone aggregate 40 mm nominal size in foundation and plinth	100	Cum	403.10	370%	1894.570	189457.000	0.00	250.00	0.00	4738
4	10.53	Cement concrete 1:4:8 with stone aggregate 20 mm nominal size in first storey upto 4 metres above plinth level	220	Cum	426.25	370%	2003.375	440742.500	0.00	80.00	0.00	1802
5	10.56	Cement concrete 1:1.5:3 with stone aggregate 20mm nominal size for reinforced concrete work in footings, strips, foundations, beams, rafts, pedestal and approach slabs of bridges etc. excluding steel reinforcement but including centering and shuttering la	0	Cum	436.45	370%	2051.315	0.000	0.00	25.00	0.00	512
6	10.90 + 10.95 (a) + note (a)	Cement concrete 1:1.5:3 with stone aggregate 20mm nominal size for reinforced concrete work for walls exceeding 20cm thickness (straight and curved) beams, girders, stairs, columns (square or rectangular) battens and lintels etc. excluding steel reinforcement	350	Cum	780.00	370%	3666.000	1283.00.000	0.00	800.00	0.00	29328
6.1	10.86+	-do- (first storey)	325	Cum	1188.75	370%	5587.125	1815815.625	0.00	143.00	0.00	79899
6.2	10.86+ 10.95 (a) + note (v)(b)	-do- (second storey)	325	Cum	1196.05	370%	5621.435	1826966.375	117.00	0.00	657707.90	
6.3	10.86+ 10.95 (a) + note (v)(b)	-do- (third storey)	325	Cum	1203.35	370%	5655.745	1838117.125	22.00	0.00	124426.39	
6.4		fourth storey	325	Cum	1210.65	370%	5690.055	1849267.875	132.00	0.00	751087.26	
6.5		fifth storey	6	Cum	1217.55	370%	5724.365	34346.190	6.00	0.00	0.00	
7	10.82 + 10.82 + 10.95 (a) + 10.95 (a)	Cement concrete 1:1.5:3 with stone aggregate 20mm nominal size for reinforced concrete work in slab with inclination not exceeding 25 degree with horizontal, excluding steel reinforcement but including centering and shuttering laid in position complete in all respect	382	Cum	1084.80	370%	5098.560	1947649.920	62.00	0.00	316110.72	
7.1	10.82 + 10.95 (a)	-do- (first storey)	382	Cum	1084.80	370%	5098.560	1947649.920	62.00	0.00	316110.72	
7.2	10.82 + 10.95 (a) + note (v)(b)	-do- (second storey)	382	Cum	1092.10	370%	5132.870	1960756.340	11.00	0.00	574881.44	
7.3	10.82 + 10.95 (a) + note (v)(b)	-do- (third storey)	382	Cum	1099.40	370%	5167.180	1973862.760	11.00	0.00	578724.16	
7.4		fourth storey	300	Cum	1106.70	370%	5201.490	1560447.000	0.00	110.00	0.00	572

(BASED ON HSR-1988 & LATEST SANCTIONED PREMIUM W.E.F. 01-01-2008)											
Sl. No.	Particulars	Unit	Rate	Quantity	Amount	Rate	Quantity	Amount	Rate	Quantity	Amount
8	Cold twisted deformed (ribbed/for steel) bars for R.C.C. works where not included in the complete rate of R.C.C. including bending, binding and placing in position complete.	4850	Qtl	917.05	3897.483	18123200.825	6410.00	0.00	1780.00	0.00	0.00
9	Cement concrete 1:4:8 with brick ballast 40mm nominal size in foundation and plinth	70	Cum	385.25	1810.875	126747.250	0.00	70.00	0.00	126747.25	0.00
10	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in pavements, roads, taxi tracks and runways, laid to required slope and camber, including consolidation, finishing, and tamping complete.	270	Cum	729.30	3427.710	925481.700	550.00	0.00	280.00	0.00	0.00
11	Damp proof course 40mm thick of cement concrete 1:2:4 using stone aggregate 20mm nominal size with 2 coats of bitumen 20/30 penetration at 1.65kg per sqm, laid hot and sanded.	250	Sqm	35.05	164.735	4103.750	250.00	0.00	0.00	0.00	0.00
12	First class brickwork laid in cement sand mortar 1:6 in foundation and plinth.	715	Cum	393.45	1770.525	1265925.375	550.00	185.00	0.00	292136.63	0.00
13	First class brickwork laid in cement sand mortar 1:6 in first storey upto 4 meter above plinth level.	277	Cum	414.45	1865.025	515611.925	277.00	0.00	0.00	0.00	0.00
13.1	-do- (first storey)	269	Cum	422.70	1902.150	511678.350	207.00	0.00	28.00	0.00	0.00
13.2	-do- (second storey)	216	Cum	430.95	1939.280	418884.480	280.00	0.00	64.00	0.00	0.00
13.3	-do- (third storey)	315	Cum	432.20	1978.400	622566.000	250.00	65.00	0.00	128466.00	0.00
13.4	fourth storey	44	Cum	447.45	2013.530	88595.320	220.00	0.00	178.00	0.00	0.00
13.5	fifth storey										
14	11.43 cm thick brick wall laid in cement sand mortar 1:4 in superstructure in first storey	2390	Sqm	55.10	247.950	592600.500	2390.00	0.00	0.00	0.00	0.00
14.1	11.48 (a)	2160	Sqm	56.05	252.225	544806.000	2160.00	0.00	0.00	0.00	0.00
14.2	11.48 (a) + note (iv)(a)	2030	Sqm	57.00	256.500	520695.000	2030.00	0.00	0.00	0.00	0.00
14.3	third storey	2030	Sqm	57.22	260.775	529373.250	2030.00	0.00	0.00	0.00	0.00
14.4	fourth storey										
18	Top Khurra 0.6 m x 0.6 m for rain water pipe in 25mm thick cement concrete 1:2:4 over 50mm thick cement concrete 1:8:16.	45	Each	12.30	36.900	1660.500	50.00	0.00	5.00	0.00	0.00
19	Sand filling under floor i/c laying consolidation, compaction & watering etc.	5400	Cum	160.00	160.000	864000.000	5400.00	0.00	0.00	0.00	0.00
20	Providing and lying cinder concrete in cement 1:15, 1 cement and 15 cinder, on terraced roofs and 1st storey, laid to slope, including consolidating the same.	80	Cum	216.65	649.950	51996.000	80.00	0.00	0.00	0.00	0.00
20.1	13.6F+note iii	80	Cum	219.65	658.950	52716.000	80.00	0.00	0.00	0.00	0.00
20.2	13.6G+note iii	90	Cum	222.65	667.950	53436.000	80.00	0.00	0.00	0.00	0.00
20.3	13.6H+note iii	2340	Sqm	36.95	173.665	406376.100	2340.00	0.00	0.00	0.00	0.00
21	Base course of floors consisting of 100mm thick cement concrete 1:8:16 and 100mm sand or stone filling.										
22	14.1 screed of 50mm of thick cement concrete 1:8:16 to be laid below the topping.										

(B) BIDDING ON HS 13399 & LATEST SANCTIONED PREMIUM W.E. 01-01-2006									
22.1	note(1)								
22.2	-do- (third storey)	2340	Sqm	15.65	370%	73.555	172118.700	1590.00	750.00
22.3	forth storey	1340	Sqm	15.95	370%	74.965	103453.100	1920.00	0.00
23	conglomerate floor 25mm thick cement concrete topping 1:2:4.	1350	Sqm	16.25	370%	78.375	103106.250	1490.00	140.00
23.1	-do- (first storey)	47	Sqm	22.40	370%	105.280	4948.160	47.00	0.00
23.2	-do- (second storey)	47	Sqm	22.70	370%	108.690	5014.430	47.00	0.00
23.3	-do- (third storey)	47	Sqm	23.00	370%	108.100	5080.700	47.00	0.00
23.4	forth storey	47	Sqm	23.30	370%	109.510	5146.970	47.00	0.00
24	Floating coat of 1.50mm thick neat cement laid in one operation to the topping.								
14.3		200	Sqm	3.70	370%	17.390	3478.000	200.00	0.00
25	Kotah stone flooring minimum 25mm thick in any pattern as specified over 20 mm thick base of cement coarse sand mortar 1:3 laid and jointed with neat cement slurry mixed with pigment to match the shade of stone including rubbing and polishing								
14.62									
25.1	-do- (first storey)	1716	Sqm	201.95	135%	474.583	814383.570	280.00	1436.00
25.2	-do- (second storey)								
14.62+note (1)		1391	Sqm	202.25	135%	475.288	661124.913	0.00	1391.00
25.3	-do- (third storey)								
14.62+note (1)		1280	Sqm	202.55	135%	475.993	609270.400	0.00	1280.00
25.4	forth storey	1290	Sqm	202.95	135%	476.690	614930.100	0.00	1290.00
26	Extra for Kotah stone flooring in treads of steps not exceeding 30 cm in width	152	sqm	1.15	135%	2.705	410.780	0.00	152.00
27	Extra for nosing in treads of steps of Kotah stone slab	350	mt	6.10	135%	14.335	5017.250	0.00	350.00
28	Kota stone 20 mm thick in skirting, risers of steps, dados and wall facing (lining) and pillars laid on 12 mm thick cement coarse sand mortar 1:3 laid and jointed with neat cement slurry mixed with pigment to match the shade of stone including rubbing								
14.66									
28.1	-do- (first storey)	200	Sqm	237.00	135%	556.950	111390.000	5.00	195.00
28.2	-do- (second storey)								
14.66+note (1)		180	Sqm	237.30	135%	557.655	100377.900	0.00	180.00
28.3	-do- (third storey)								
14.66+note (1)		172	Sqm	237.60	135%	558.360	96037.920	0.00	172.00
28.4	forth storey								
14.66+note (1)		173	Sqm	237.90	135%	559.060	96717.350	0.00	173.00
29	12mm thick cement plaster 1:4 on wall								
15.5									
29.1	-do- (first storey)	1835	Sqm	12.70	325%	53.975	99044.125	2410.00	0.00
29.2	-do- (second storey)	1835	Sqm	12.88	325%	54.740	100447.900	2370.00	0.00
29.3	-do- (third storey)	1750	Sqm	13.06	325%	55.505	97133.750	2290.00	0.00
29.4	forth storey	2310	Sqm	13.24	325%	47.550	109840.500	2070.00	0.00
29.5	fifth storey	250	Sqm	13.42	325%	48.310	12077.500	0.00	250.00
30	15mm thick cement plaster 1:4 on the rough side of singe or half brick								
15.10									
30.1	-do- (first storey)	4035	Sqm	15.65	325%	66.610	268045.375	4100.00	0.00
30.2	-do- (second storey)								
15.10+note (1)		3540	Sqm	15.83	325%	67.278	278162.350	3240.00	0.00
30.3	-do- (third storey)								
15.10+note (1)		3060	Sqm	16.01	325%	68.043	208210.050	3320.00	0.00
30.4	forth storey								
15.10+note (1)		3370	Sqm	16.19	325%	57.980	195392.600	3560.00	0.00
30.5	fifth storey								
15.10+note (1)		195	Sqm	16.37	325%	58.750	11456.250	1150.00	0.00

-21-

BASED ON HSN 2508 & LATEST SANCTIONED PREMIUM W.E.F. 01-01-2008										
Sl. No.	Particulars	Unit	Rate	Qty	Amount	Rate	Qty	Amount	Rate	Qty
31	with mixture of sand and gravel or crushed stone graded from 2.36mm to 12mm nominal size dashed over and i/c fresh plaster in 2 coats 10mm cement plaster 1:4 and finished coat 10mm cement plaster with cement mortar	Sqm	35.40	325%	150.450	481440.000	0.00	3200.00	0.00	0.00
31.1	-do- (first storey)	Sqm	35.58	325%	151.215	257821.575	0.00	1705.00	0.00	0.00
31.2	-do- (second storey)	Sqm	35.76	325%	151.980	197574.000	0.00	1300.00	0.00	0.00
31.3	-do- (third storey)	Sqm	35.94	325%	57.980	75374.000	0.00	1300.00	0.00	0.00
31.4	fourth storey	Sqm	36.12	325%	58.750	14687.500	0.00	250.00	0.00	0.00
31.5	fifth storey	Sqm								
32	10 mm thick cement plaster 1:4 under side & ceiling	Sqm	12.65	325%	53.763	117202.250	2250.00	0.00	70.00	0.00
32.1	-do- (first storey)	Sqm	12.83	325%	54.528	102511.700	2395.00	0.00	515.00	0.00
32.2	-do- (second storey)	Sqm	13.01	325%	55.293	74091.950	2395.00	0.00	1055.00	0.00
32.3	-do- (third storey)	Sqm	13.19	325%	45.640	61157.600	1880.00	0.00	540.00	0.00
32.4	fourth storey	Sqm	13.37	325%	46.400	2784.000	100.00	0.00	20.00	0.00
32.5	fifth storey	Sqm								
33	20mm thick cement plaster damp proof course 1:3 with 2 coats of bitumen at 1.65 Kg. per laid hot and sanding	Sqm						0.00	0.00	0.00
(a)	Vertical							0.00	0.00	0.00
(a)+note (i)								0.00	0.00	0.00
	- do - (second storey)	Sqm	30.88	325%	131.240	29529.000	225.00	0.00	0.00	0.00
	- do - (third storey)	Sqm	31.06	325%	132.005	23760.900	180.00	0.00	0.00	0.00
	- do - (fourth storey)	Sqm	31.24	325%	132.770	23898.600	180.00	0.00	0.00	0.00
b)	Horizontal									
(b)+note (i)										
	- do - (second storey)	Sqm	29.13	325%	123.803	16094.325	170.00	0.00	40.00	0.00
	- do - (third storey)	Sqm	29.31	325%	124.588	16193.775	170.00	0.00	40.00	0.00
	- do - (fourth storey)	Sqm	29.49	325%	125.333	16293.225	170.00	0.00	40.00	0.00
34	Providing and fixing 12 mm thick and 100 mm wide peimet with 25 mm diameter wooden curtain rod and brackets, including fixing with 25 mm x 3 mm M.S flat 10 cm long and plugs (Teak)etc, complete.									
17.58(d)	Teak wood	Metre	51.20	175%	147.350	174315.050	1183.00	0.00	0.00	0.00
35	Providing and fixing six-levers brass 10cm mortice latch and lock, and a pair of lever handles with necessary screws, etc complete (Indian make of reputed firm, such as Godrej or equivalent)									
17.73	Providing and fixing 150mm hasps and staples with necessary screws, etc complete	each	134.45	175%	235.288	4705.750	20.00	0.00	0.00	0.00
17.78 (c)	Supplying and fixing hydraulic door closer I.S.I. mark, with necessary screws, etc Complete -	each	4.00	175%	7.525	2257.500	585.00	0.00	285.00	0.00
17.82	I.S.I. designation No III (size of door 851 mm to 1000 mm)							0.00	0.00	0.00
(c)	Factory manufactured solid flush door shutters with black board, core as per I.S. No. 1659-1969 bounded with water proof type phenol formaldehyde synthetic resin, hot pressed, conforming to I.S.2202 part I and II, fixed in position i/c iron hinges.	Each	216.50	175%	378.875	4546.500	12.00	0.00	0.00	0.00
38										
17.93(a)-note (i) cf 17.18										

ANCIENT PRE-W. 200									
Commercial venting with vertical grans or cross bands and face veneer on both sides commercial facing its laminated core and lipped edges.									
(a)									
38.1 (iii)	35mm thick	1436	Sqm	436.15	150%	1090.375	1565778.500	1436.00	0.00
38.2 a (i)	25mm thick	615	Sqm	387.15	150%	967.875	795243.125	700.00	0.00
39	Providing and fixing .50mm thick aluminium sheet i/c cost of necessary screws etc. complete.							85.00	0.00
40	Providing and fixing sliding bolt with nuts and screws etc. complete	130	Sqm	90.55	175%	249.013	32371.625	150.00	0.00
(C)	Iron								0.00
40.1 (i)	Size 300 x 16mm	662	Each	17.45	175%	47.988	31767.725	662.00	0.00
40.2 (ii)	Size 210x16mm	180	Each	16.35	175%	44.963	8093.250	180.00	0.00
41	Cost of iron fittings complete for doors and windows, such as lower bolts, handles etc., and screws for these fittings (excluding sliding bolt)							0.00	0.00
41.1 17.71 (a)	For single leaf shutter	1436	Sqm	6.40	175%	17.600	25273.600	1870.00	0.00
41.2 17.71 (b)	For double leaf shutter	600	Sqm	10.15	175%	27.913	16747.500	1600.00	0.00
42 18.12	Wrought iron and mild steel (using angles, thick garage doors, with 40mm x 40mm x 6mm angle iron frame with diagonal braces, 3mm thick gusset plates at the junctions, hooks at the top and 25 mm dia. pulleys, & T-iron 50 mm x 50mm x 6mm guides at bottom included	280	Q'l	1040.35	325%	4421.488	1238016.500	215.00	0.00
43	Providing and fixing G.I. sheet 0.80 mm thick							0.00	287396.69
44	Providing and fixing in position collapsible steel shutters, with vertical channels 20 mm x 10 mm x 2mm and braced with flat iron diagonal 20 mm x 5 mm size, with top and bottom rails of T-iron 40 mm x 40 mm x 6 mm with 38 mm dia steel pulleys, complete w.	9.5	Sqm	424.00	325%	1378.000	13091.000	0.00	13091.00
45	Factory manufactured panelled door or glazed window shutter of commercial hard wood such as hollock, champ, chikrassy and chaplash etc (non - confireous timber other than teak conforming to I.S. specification no. 1003 kiln seasoned) with 100mm vide vertical styles, 150mm vide lock rail, 200mm vide bottom rail & 100mm vide others rail with panalles of 15mm thick, tongued and grooved of commercial hard wood i/c the cost of iron hinges, screws, chocks/cleats, stops, nails etc complete fixed in position excluding the cost of any fittings other than specified above b it including the labour for fixing the same in position. 35 mm thick	9.5	Sqm	305.45	325%	992.713	9430.769	0.00	9430.77
17.90 (b) note 1 of 17.18		600	Sqm	424.15	175%	1166.413	699847.500	430.00	198290.13
46	S/F glass panes including special metal sash putty of approved make								0.00
18.30	Glass panes 4mm thick, exceeding 40 sq.dn.area	600	Sqm	115.40	325%	490.450	294270.000	600.00	0.00
(b)									0.00

[illegible]

Sl. No.	Particulars	Unit	QTY	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount</
---------	-------------	------	-----	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	--------	------	----------

96

Item No. 14.4 To consider & approve the revised cost estimate for the construction of MBA/MCA Block – a Two storey framed structure Building at NIT, Kurukshetra.

The B & WC in its 11th meeting held on 28.07.2009 approved the preliminary cost estimate of Rs.526.3 lac for the construction of MBA/MCA Building at NIT, Kurukshetra.

The work of the above said building is under construction, during execution of this work quantities of a few items have increased because of detailed structural design and drawings & design and in addition of a few items as suggested by the architects and request made by Head of Departments of Computer Applications and Business Administration for the provision of false ceiling in this building.

In view of the circumstances explained as above the revised cost estimate amounting to Rs.586.48 lac. has been framed and duly scrutinized by the Construction Cell to cover the cost of additional items & quantities.

It is therefore requested that B & WC may kindly consider and approve the revised cost estimate amounting to Rs.586.48 lac. for the above cited work.

Sr. No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Total Rate	Estimated Cost	Qty. Likely to be Executed	Qty. in Saving	Qty. in Excess	Saving Amount Rs.	Excess Amount Rs.
SUB PART-III: INTERNAL PH SERVICES (SCHEDULE ITEMS)													
1	30.41	P/F in position best Indian make lavatory Suites											
	(iv)	White											
		Size 550mmx400mm with one no. tap	36	Each	407.00	25.0%	1424.50	51282	36.00	0.00	0.00	0.00	0
2	30.45	Providing and fixing in position best Indian make chromium plated brass 2nd tap for lavatory suite.	36	Each	92.00	250%	322.00	11592	36.00	0.00	0.00	0.00	0
3	30.48	P/F in position 32mm diameter G.I. waste pipe embedded in wall	32	Each	98.00	250%	343.00	10976	36.00	0.00	4.00	0.00	0
4	30.50	P/F in position best Indian make C.P. brass bottle traps 32mm diameter	32	Each	92.00	250%	322.00	10304	36.00	0.00	4.00	0.00	0
5	30.67	P/F in position best Indian make paper holder fixed into C.P. including cutting & making good the wall etc.											
	(a)	C.P. brass	34	Each	27.50	250%	96.25	3273	34.00	0.00	0.00	0.00	0
6	30.69	P/F in position glass shelf fixed in with rawl plugs with C.P. brass screws complete including cutting & making good the walls etc.											
	(a)	With C.P. brass bracket and guard rail											
7	30.71	(i) 600mm x 125mm P/F in position best Indian make bevelled edge 5.5mm thick mirror fixed in position by means of 4 nos. C.P. brass screws and washers complete including cutting and making good the walls etc.	32	Each	72.50	250%	253.75	8120	32.00	0.00	0.00	0.00	0
	(a)	Indian make											
	(i)	600 mm x 450mm	32	Each	107.00	25.0%	374.50	11984	36.00	0.00	4.00	0.00	0
8	30.74	Providing and fixing in position super quality 65 mm I/d opening CP brass dome type hinged grating weighting about 750 gms. Fixed in cement mortar 1:2 corn. Lete in all respects (as required by the Engineer-in-charge).	40	Each	67.50	250%	236.25	9450	40.00	0.00	0.00	0.00	0
9	30.75(a)	Providing & fixing in position 15mm I/d C.P. brass bib cocks of best quality (as required by the Engineer-in-charge)											
	(a)	Bib cock long body	36	Each	15.60	250%	406.00	14616	20.00	16.00	0.00	0.00	6496
	(C)	Bib cock	0	Each	100.00	250%	350.00	0	36.00	0.00	36.00	0.00	0

Sr. No.		HSR No.	Description	Qty.	Unit	Rate	C.P.	Total Rate	Estimated Cost	Qty. Likely to be Executed	Qty. In Saving	Qty. In Excess	Saving Amount Rs.	Excess Amount
SUB PART-III: INTERNAL PH SERVICES (SCHEDULE ITEMS)														
10	30.76		P/F in position C.P. brass stop cocks (as approved by Engineer-in-charge)											
	(a)		15mm stop cocks								0.00		0	
	(ii)		Concealed stop cocks with flange	62	Each	130.00	250%	455.00	282.10	40.00	0.00	0.00		
11	30.84		P/F in position HCI soil, waste, vent pipes to ISI specification or any other reputed firm including cutting & wastage etc. & cutting holes in walls, roofs or floor etc. and making good the floor & wall but excluding cost of lead jointing.											
	(a)		100mm internal diameter	300	Mtr.	97.50	300%	390.00	117000	300.00	0.00			
	(u)		75mm internal diameter	600	Mtr.	83.00	300%	332.00	199200	200.00	0.00	0.00	0	
12	30.87		Providing lead caulked joints to HCI pipes & specials conforming to ISI specification of ELC or any other reputed firm including cost of lead varn. fuel & tools etc.										132800	
	(a)		100mm internal diameter (1.13 kg)	180	Each	33.50	225%	108.88	19598	250.00	0.00	70.00	0	70.00
	(b)		75 mm internal diameter (0.91 kg)	260	Each	27.50	225%	89.38	23238	200.00	60.00	0.00	5362.5	
13	30.88		Providing and fixing in position MS or Heavy flat iron clamps made out of MS flat not less than 5 mm of the approved design for fixing CI Soil waste vent or anti pipes to walls complete in all respects including cutting and making good the walls and floors etc. and painting											
	(a)		For 100 mm internal diameter pipes	120	Each	12.50	300%	50.00	6000	120.00	0.00	0.00	0	
	(b)		For 75 mm internal diameter pipes	90	Each	11.00	300%	44.00	3960	90.00	0.00	0.00	0	
14	30.89		P/F HCI floor trap ISI marked of the self-cleaning design with C.P. brass hinged grating with or without vent arm & including cement concrete 1:2:4 complete in all respects											
	(b)		With 75mm internal diameter outlet	56	Each	105.00	300%	420.00	23520	56.00	0.00	0.00	0	

- 31 -

(BASED ON HSR-1988 & LATEST SANCTIONED PREMIUM W.E.F. 01-02-2009)													
Sr. No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Total Rate	Estimated Cost	Qty. Likely to be Executed	Qty. In Saving	Qty. in Excess	Saving Amount Rs.	Excels Amount
SUB PART-III: INTERNAL PH SERVICES (SCHEDULE ITEMS)													
15	30.90	PROVIDING AND FIXING IN POSITION HCI 50mm INTERNAL DIAMETER OUTLET PLAIN NAHAN TRAP ISI Marked of the self cleaning design with CP BRASS HINGED GRATING WITH FRAME WEIGHING 6.80 KG EACH FIXED complete as fully described in item no. 30.89 above.	16	Each	100.00	300%	400.00	6400	16.00	0.00	0.00	0	
16	30.91	P/F in position HCI specials for waste vent pipes to ISI specification including cutting holes in walls & making good but excluding cost of lead joints											
	(a)	For 100mm internal diameter pipes											
	(i)	Heal rest	26	Each	58.00	300%	232.00	6032	18.00	8.00	0.00	1856	
	(ii)	Double junction with door 100mmx100mmx100mm	24	Each	99.00	300%	396.00	9504	0.00	24.00	0.00	9504	
	(iii)	Pass over pipe	24	Each	86.50	300%	3416.00	8304	0.00	24.00	0.00	8304	
	(vi)	Single junction with door 100x100x100mm	24	Each	76.50	300%	306.00	7344	18.00	6.00	0.00	1836	
	(v)	Double junction plain 100x100x100mm	2	Each	60.00	300%	240.00	480	0.00	2.00	0.00	480	
	(vi)	Single junction plain 100x100x100mm	4	Each	53.00	300%	212.00	848	0.00	4.00	0.00	848	
	(vii)	Single junction with door 100x100x50mm	16	Each	39.50	300%	158.00	2528	0.00	16.00	0.00	2528	
	(viii)	Double junction with door 100mmx100mmx50mmx50mm	16	Each	36.50	300%	146.00	2336	0.00	16.00	0.00	2336	
	(ix)	Single junction with door 100x100x50mm	20	Each	27.50	300%	110.00	2200	0.00	20.00	0.00	2200	
	(xvi)	Cowls	0	Each	36.50	300%	146.00	0	18.00	0.00	18.00	0	
	(xxii)	Collars	0	Each	27.50	300%	110.00	0	20.00	0.00	20.00	0	
	(b)	For 75mm internal diameter pipes											
	(i)	Heal rest	32	Each	39.50	300%	158.00	5056	15.00	17.00	0.00	2686	
	(iv)	Single junction with door 75mmx75mmx75mm	22	Each	59.00	300%	236.00	5192	15.00	7.00	0.00	1652	
	(iii)	Bend with door	24	Each	42.00	300%	168.00	4032	0.00	24.00	0.00	4032	
	(vi)	Bend plain	22	Each	39.50	300%	158.00	3476	0.00	22.00	0.00	3476	
	(v)	Terminal guard	2	Each	27.50	300%	110.00	220	0.00	2.00	0.00	220	
	(vi)	Cowls	2	Each	28.00	300%	112.00	224	15.00	0.00	13.00	0	
	(vii)	Collars	18	Each	22.50	300%	90.00	1620	15.00	3.00	0.00	270	

- 32 -

(BASED ON HSR-1988 & LATEST SANCTIONED PREMIUM W.F.F. 2000)

Sr. No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Total Rate	Estimated Cost	Qty. Likely to be Executed	Qty. in Saving	Qty. in Excess	Saving Amount Rs.	Excess Amount
S/B PART-III: INTERNAL PH SERVICES (SCHEDULE ITEMS)													
17	30.95	Cutting chase in brick wall in cement for embedding G.I. or HCl pipe lines & making good the same	172	Mtr.	6.00	250%	21.00	3612	172.00	0.00	0.00	0	
18	(a) 30.101	Size: 75x75mm Painting HCl soil waste and vent pipes and fittings with black bitumastic ordinary paint of approved manufacture two coats on new work.	240	MTR	1.85	250%	6.48	1554	240.00	0.00	0.00	0	
	(b) 30.110	(b) 75 mm internal diameter P/F in position automatic brass ball valves in tanks	218	MTR	1.75	250%	4.73	1030	218.00	0.00	0.00	0	
	(b)	With plastic ball											
20	30.114	(iii) 25mm diameter P/F in position Gully traps fixed in cement concrete 1:4:8 with HCl grating 150x150mm CI cover weighing approximately 7.26 kg & frame clear opening 300 x 300mm and chamber including cost of brick work 1:5 cement concrete 1:8:16 and C.C. 1:2:4 in coping	10	Each	39.00	250%	136.50	1365	10.00	0.00	0.00	0	
21	(b) 30.115	100mm internal diameter HCl gully traps Providing and fixing in position best Indian make vitreous china ware channel of size 600 mm x 15C including laying and fixing in cement concrete 1:2:4 complete as required by the Engineer-in-charge.	22	Each	208.00	300%	832.00	18304	16.00	6.00	0.00	4992	0
22	(i) 28.24	White Cutting holes upto 23cm through brick work in cement wall for pipes and making good	20	Each	92.00	250%	322.00	6440	20.00	0.00	0.00	0	
23	(a) 29.84	11.43cm thickness of walls 22.86 cm. thickness of walls Constructing brick masonry inspection chamber upto 60 mtr. depth in cement mortar 1:5 cement concrete 1:2:4 benching, 12mm thick cement plaster, RCC 1:2:4 slab 100mm thick with 455x455 mmx455x610mm inside light duty GI inspection chamber cover & frame with 3 coats of black bitumastic paint	16	Each	14.00	250%	43.00	784	16.00	0.00	0.00	0	
	(b)		16	Each	20.35	250%	71.23	1140	16.00	0.00	0.00	0	
(c)		Size 600x900mm inside	18	Each	690.00	375%	3277.50	58995	12.00	6.00	0.00	19665	

25

Construction of Block A & Block B Two Storey named structure bearing at KURUR TR													
(BASED ON HSR-1988 & LATEST SANCTIONED PREMIUM W.E.F. 01-02-2009)													
Sl. No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Total Rate	Estimated Cost	Qty. Likely to be Executed	Qty. in Saving	Qty. in Excess	Saving Amount Rs.	Excess Amount
SUB PART-III: INTERNAL PH SERVICES (SCHEDULE ITEMS)													
24	29.85	Extra for every 0.30 mts. depths of inspection chamber											
	(c)	600mmx900mm	18	Each	139.00	375%	660.25	11885	25.00	0.00	7.00	0	46
25	6.8	Excavation for pipelines running under pressure in trenches and pits in open areas where disposal of surplus earth is done along with the alignment and restoration of unmetalled surface to the original condition											
	(a)	Without timbering and shoring upto 1.5 meters depth	225	100 Cum	1030.00	300%	4120.00	9270	25.00	200.00	0.00	8240	
26	6.10	Excavation of trenches in street lanes or in open area for storm sewer, sewers running by gravity & man holes to full depth and removal of surplus soil upto to a lead of 1Km in ordinary soil											
	(a)	For depth of excavation not exceeding 3 mts. below ground level	195	100 Cum	1189.00	300%	4756.00	9274	100.00	95.00	0.00	4518.2	
27	10.39	Cement concrete 1:4:8 with stone aggregate 40mm nominal size in foundation and plinth	46	Cum	403.10	340%	1773.64	81587	15.00	31.00	0.00	54982.84	
28	10.41	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in foundation and plinth	25	Cum	615.60	340%	2708.64	67716	5.00	20.00	0.00	54172.8	
29	10.59	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in first storey upto 4 metres above plinth level											
	10.50+ note (v)(b)	-do- (first storey)	1	Cum	621.85	340%	2736.14	2736	1.00	0.00	0.00	0	
	10.50+ note (v)(b)	-do- (second storey)	2	Cum	624.40	340%	2747.36	5495	2.00	0.00	0.00	0	
30	30.83	Providing and fixing in position best Indian make CP brass inlet connection 15mm with 375mm pipe and CP Brass nuts.	0	Each	115.00	250%	402.50	0	122.00	0.00	122.00	0	
31	30.26	Providing & fixing in position best Indian make a range of two urinals large flat back or angular lipped front 610 mm high in vitreous chinaware with 5 liters capacity best Indian make C.I. automatic flushing cistern with fittings and flush pipe etc. completes as fully described in item no-30.25 above Range of two Urinals											
	(a)	White	0	Each	1327.00	250%	6394.50	0	8.00	0.00	8.00	0	

CC Application No. [] A & [] Block [] to Stc. [] at [] KURUKH TRA (BASED ON HSR-1988 & LATEST SANCTIONED PREMIUM W.E.F. 01-02-2009)													
Sr. No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Total Rate	Estimated Cost	Qty. Likely to be Executed	Qty. In Saving	Qty. in Excess	Saving Amount Rs.	Excess Amount : Rs.
SUB PART-III: INTERNAL PH SERVICES (SCHEDULE ITEMS)													
32	30.37	Extra for providing and fixing vitreous automatic flushing cistern including fittings and brackets instead of CI flushing cistern complete.	0	Each	201.00	250%	703.50	0	14.00	0.00	14.00	0	9849
33	(b) (i) 30.2	10 Ltrs capacity Cistern white P/f in position best Indian type Orissa or Oriya water closet suite complete with 100mm HCl "P" trap and all other necessary fittings as per 30.1(Full @ 925. each)	0	Each	925.00	250%	3237.50	0	6.00	0.00	6.00	0	1942
		TOTAL SCHEDULE ITEMS:						899304.15				343467.34	164820.00
								Saving in Schedule items					178647.3
								Add 32%					57157.1
								Total Saving					235814.4

← 35

KURUKSHETRA

(BASED ON HSR-1988 & LATEST SANCTIONED PREMIUM W.E.F. 01-02-2009)

Sr. No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Total Rate	Estimated Cost	Qty. Likely to be Executed	Qty. in Saving	Qty. in Excess	Saving Amount Rs.	Excess Amount R.
SUB PART-III: INTERNAL PH SERVICES (NON SCHEDULE ITEMS)													
1	NS	Providing & fixing 1 white vitreous (European type) water closet litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete including painting oos fittings and brackets, cutting and making good the walls and floors wherever required.	36	Each	5000.00		5000.00	180000	34	2	0	10000	
2	N.S	Providing & laying Cement Concrete 1:2:4 75mm in bed and around C.I. Soil waste pipe 100mm and 75mm i/d under floor including centering and shuttering where required.	135	Mtr.	300.00		300.00	40500	120	15	0	4500	
	(a)	100mm dia	160	Mtr.	240.00		240.00	38400	90	70	0	16800	
3	NSR	Providing, laying, jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement, 1 fine sand) including testing of joints etc. complete.											
		150mm i/d	100	Mtr.	150.00		150.00	15000	100	0	0	0	
	(b)	200mm i/d	250	Mtr.	230.00		230.00	57500	50	200	0	46000	
4	NS	Providing and fixing of G.M. Peat valves heavy patterns with hand wheels ISI marked to GI pipe lines.											
	(a)	25mm i/d	20	Each	350.00		350.00	7000	20	0	0	0	
	(b)	40mm i/d	20	Each	900.00		900.00	18000	20	0	0	0	
	(c)	50mm i/d	20	Each	1250.00		1250.00	25000	5	15	0	18750	
5	NSR	Providing, testing and fixing in position G.I. pipe 'B' class medium duty in ground including cost of specials such as elbow, bend, tees etc. cutting, threading complete in all respect to the satisfaction of Engineer-in-charge											
		15 mm i/d	400	Mtr.	120.00		120.00	48000	150	250	0	30000	
		20 mm i/d	750	Mtr.	144.00		144.00	52800	200	550	0		

		15 mm i/d	19 mm i/d	25 mm i/d	30 mm i/d	40 mm i/d	50 mm i/d	60 mm i/d	75 mm i/d	100 mm i/d	125 mm i/d	150 mm i/d	175 mm i/d	200 mm i/d	225 mm i/d	250 mm i/d	275 mm i/d	300 mm i/d	350 mm i/d	400 mm i/d	450 mm i/d	500 mm i/d	600 mm i/d	750 mm i/d	900 mm i/d	1000 mm i/d	1200 mm i/d	1500 mm i/d	1800 mm i/d	2000 mm i/d	2250 mm i/d	2500 mm i/d	3000 mm i/d	3500 mm i/d	4000 mm i/d	4500 mm i/d	5000 mm i/d	6000 mm i/d	7500 mm i/d	9000 mm i/d	10000 mm i/d	12000 mm i/d	15000 mm i/d	18000 mm i/d	20000 mm i/d	22500 mm i/d	25000 mm i/d	30000 mm i/d	35000 mm i/d	40000 mm i/d	45000 mm i/d	50000 mm i/d	60000 mm i/d	75000 mm i/d	90000 mm i/d	100000 mm i/d	120000 mm i/d	150000 mm i/d	180000 mm i/d	200000 mm i/d	225000 mm i/d	250000 mm i/d	300000 mm i/d	350000 mm i/d	400000 mm i/d	450000 mm i/d	500000 mm i/d	600000 mm i/d	750000 mm i/d	900000 mm i/d	1000000 mm i/d	1200000 mm i/d	1500000 mm i/d	1800000 mm i/d	2000000 mm i/d	2250000 mm i/d	2500000 mm i/d	3000000 mm i/d	3500000 mm i/d	4000000 mm i/d	4500000 mm i/d	5000000 mm i/d	6000000 mm i/d	7500000 mm i/d	9000000 mm i/d	10000000 mm i/d	12000000 mm i/d	15000000 mm i/d	18000000 mm i/d	20000000 mm i/d	22500000 mm i/d	25000000 mm i/d	30000000 mm i/d	35000000 mm i/d	40000000 mm i/d	45000000 mm i/d	50000000 mm i/d	60000000 mm i/d	75000000 mm i/d	90000000 mm i/d	100000000 mm i/d	120000000 mm i/d	150000000 mm i/d	180000000 mm i/d	200000000 mm i/d	225000000 mm i/d	250000000 mm i/d	300000000 mm i/d	350000000 mm i/d	400000000 mm i/d	450000000 mm i/d	500000000 mm i/d	600000000 mm i/d	750000000 mm i/d	900000000 mm i/d	1000000000 mm i/d	1200000000 mm i/d	1500000000 mm i/d	1800000000 mm i/d	2000000000 mm i/d	2250000000 mm i/d	2500000000 mm i/d	3000000000 mm i/d	3500000000 mm i/d	4000000000 mm i/d	4500000000 mm i/d	5000000000 mm i/d	6000000000 mm i/d	7500000000 mm i/d	9000000000 mm i/d	10000000000 mm i/d	12000000000 mm i/d	15000000000 mm i/d	18000000000 mm i/d	20000000000 mm i/d	22500000000 mm i/d	25000000000 mm i/d	30000000000 mm i/d	35000000000 mm i/d	40000000000 mm i/d	45000000000 mm i/d	50000000000 mm i/d	60000000000 mm i/d	75000000000 mm i/d	90000000000 mm i/d	100000000000 mm i/d	120000000000 mm i/d	150000000000 mm i/d	180000000000 mm i/d	200000000000 mm i/d	225000000000 mm i/d	250000000000 mm i/d	300000000000 mm i/d	350000000000 mm i/d	400000000000 mm i/d	450000000000 mm i/d	500000000000 mm i/d	600000000000 mm i/d	750000000000 mm i/d	900000000000 mm i/d	1000000000000 mm i/d	1200000000000 mm i/d	1500000000000 mm i/d	1800000000000 mm i/d	2000000000000 mm i/d	2250000000000 mm i/d	2500000000000 mm i/d	3000000000000 mm i/d	3500000000000 mm i/d	4000000000000 mm i/d	4500000000000 mm i/d	5000000000000 mm i/d	6000000000000 mm i/d	7500000000000 mm i/d	9000000000000 mm i/d	10000000000000 mm i/d	12000000000000 mm i/d	15000000000000 mm i/d	18000000000000 mm i/d	20000000000000 mm i/d	22500000000000 mm i/d	25000000000000 mm i/d	30000000000000 mm i/d	35000000000000 mm i/d	40000000000000 mm i/d	45000000000000 mm i/d	50000000000000 mm i/d	60000000000000 mm i/d	75000000000000 mm i/d	90000000000000 mm i/d	100000000000000 mm i/d	120000000000000 mm i/d	150000000000000 mm i/d	180000000000000 mm i/d	200000000000000 mm i/d	225000000000000 mm i/d	250000000000000 mm i/d	300000000000000 mm i/d	350000000000000 mm i/d	400000000000000 mm i/d	450000000000000 mm i/d	500000000000000 mm i/d	600000000000000 mm i/d	750000000000000 mm i/d	900000000000000 mm i/d	1000000000000000 mm i/d	1200000000000000 mm i/d	1500000000000000 mm i/d	1800000000000000 mm i/d	2000000000000000 mm i/d	2250000000000000 mm i/d	2500000000000000 mm i/d	3000000000000000 mm i/d	3500000000000000 mm i/d	4000000000000000 mm i/d	4500000000000000 mm i/d	5000000000000000 mm i/d	6000000000000000 mm i/d	7500000000000000 mm i/d	9000000000000000 mm i/d	10000000000000000 mm i/d	12000000000000000 mm i/d	15000000000000000 mm i/d	18000000000000000 mm i/d	20000000000000000 mm i/d	22500000000000000 mm i/d	25000000000000000 mm i/d	30000000000000000 mm i/d	35000000000000000 mm i/d	40000000000000000 mm i/d	45000000000000000 mm i/d	50000000000000000 mm i/d	60000000
--	--	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	------------	------------	------------	------------	------------	------------	------------	------------	------------	------------	------------	------------	------------	------------	------------	------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	---------------	---------------	---------------	---------------	---------------	---------------	---------------	---------------	---------------	---------------	---------------	---------------	---------------	---------------	---------------	----------------	----------------	----------------	----------------	----------------	----------------	----------------	----------------	----------------	----------------	----------------	----------------	----------------	----------------	----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	------------------	------------------	------------------	------------------	------------------	------------------	------------------	------------------	------------------	------------------	------------------	------------------	------------------	------------------	------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------	---------------------	---------------------	---------------------	---------------------	---------------------	---------------------	---------------------	---------------------	---------------------	---------------------	---------------------	---------------------	---------------------	---------------------	---------------------	----------------------	----------------------	----------------------	----------------------	----------------------	----------------------	----------------------	----------------------	----------------------	----------------------	----------------------	----------------------	----------------------	----------------------	----------------------	-----------------------	-----------------------	-----------------------	-----------------------	-----------------------	-----------------------	-----------------------	-----------------------	-----------------------	-----------------------	-----------------------	-----------------------	-----------------------	-----------------------	-----------------------	------------------------	------------------------	------------------------	------------------------	------------------------	------------------------	------------------------	------------------------	------------------------	------------------------	------------------------	------------------------	------------------------	------------------------	------------------------	-------------------------	-------------------------	-------------------------	-------------------------	-------------------------	-------------------------	-------------------------	-------------------------	-------------------------	-------------------------	-------------------------	-------------------------	-------------------------	-------------------------	-------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	----------

No.	Description	Unit	Quantity	Rate	Amount
11	Construction brick masonry hole in cement mortar 1:7 (Cement : coarse sand) R.C.C. top slab with 1:2:4 mix (1cement:2coarse sand: 4 graded stone aggregate 20mm nominal size), foundation concrete 1:4:8mix (1cement:4coarse sand :8 graded stone aggregate 40mm nominal size) Inside plastering 12mm thick with cement mortar 1:3 (1cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1cement : 2coarse sand :4 graded stone aggregate 20mm nominal size) finished with a floating coat of neat cement complete as per standard design	m ²	9000.00	9000.00	81000000.00
12	Inside Size 120x90cm and 90 cm deep including SFRC Cover with frame (Heavy duty) 580mm internal diameter	Sq.m	1	9000.00	9000.00
	With Sewer bricks	Each	1	9000.00	9000.00
	Extra for depth for manholes	Mtr.	2	2500.00	5000.00
13	Size 120x90cm With Sewer bricks Making sewer connection with the existing sewer line	Each	1	1000.00	1000.00
14	Providing M.S. foot rests including fixing in manholes with 20x20x10cm cement concrete blocks 1:3:6 (1cement:: 3 coarse sand; 6 graded stone aggregate 20mm nominal size) as per standard design :	Sq.m	30	150.00	4500.00
	With 20x20mm square bar	Each	30	150.00	4500.00
	TOTAL NON-SCHEDULE ITEMS:			913340.00	913340.00
	Total Saving				335155.00

All china ware should be of CERA/HINDWA TE/HINDUSTAN PERRYWARE Make Ist quality or as directed by the Engineer-In-Chief
All C.P. fittings/fixtures should be of SEIKO/PARKO/ Chilly make.
ALL PIPE SHOULD BE JINDAL / TATA MAKE or as directed by the Engineer- In-Chief

Sr. No.		MSR No.	Description	Qty.	Unit	Non Schedule Items		Qty. to be deducted		Saving amount		Excess amount
						Rate	Amount					
SUB PART-I: INTERNAL CIVIL WORKS (SCHEDULE)												
53	NS		Providing and fixing aluminium work for doors windows . Ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to plugs and screws or with fixing clips. Or with expansion hold fasteners including necessary filling up of gaps at junctions. at top bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight mitred and jointed mechanically wherever required including cleat angle , panelling. C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer -in -charge. (Glazing and panelling to be paid for separately) Finish of 15 micron (Jindal Co. Make)									
			For fixed portion									
	NS(a)		Anodised aluminium (anodised transparent or dyed to required shade according to IS:1868, minimum anodising of grade A.C.15)	100.00	Kg	375.00	37,500.00	155.00		65.00		24,375.00
	NS(b)		For shutters of doors, window & ventilators including provision for fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of PVC/ neoprene gasket required(Fittings shall be paid for separately)	144.00	Kg	375.00	54,000.00	110.00	34.00		12,750.00	
54	NS		Providing and fixing Glazing in aluminium work for doors windows . Ventilators and shutters and partitions with PVC/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge.(cost of aluminium snap beading shall be paid in basic item)									
			With float glass panes of 5.50mm thickness	22.00	Sqm	550.00	12,100.00	30.00		8.00		4,400.00
55	NS		Providing and fixing double action hydraulic floor spring of approved brand and manufacture IS :6315 marked, for doors including cost of cutting floors as required embedding in floors and cover plates with brass pivot and single piece M.S sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge.									
			With stainless steel cover plate	4.00	Nos	1,700.00	6,800.00	8.00		4.00		6,300.00

Structure Building at NIT Kurukshetra										Qty. to be executed		Qty. in saving		Qty. in excess		Saving Amount Rs.		Excess Amount Rs.	
(BASED ON HSR-1988 & LATEST SANCTIONED PREMIUM										Non Schedule Items									
Sr. No.	HSR No.	Description	Qty.	Unit	Rate	Amount													
SUB PART-I: INTERNAL CIVIL WORKS (SCHEDULE																			
56	NS	Providing and laying polished vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorptions less than 0.08% and conforming to IS:15622 of approved make in all colours and shades laid on 20mm thick cement mortar 1:3 (1Cement 3coarse sand) including grouting the joints with white cement and matching pigments etc. complete. (made as per approval of Eng'neer-in-charge)	1875.00	Sqm	950.00	1,781,250.00	3,450.00											1,496.25	
57	NS	Size of Tile 60x60cm Providing and fixing 18mm thick mirror polished, machine cut for kitchen platforms, vanity counters facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 with joints treated with Granite stone	13.00 38.00	Sqm Mtr	2,600.00 50.00	33,800.00 5,700.00	25.00 150.00									112.00 112.00		291.20 16.80	
58	NS	Extra for providing edge moulding to granite stone counters including machine polishing to edge to give high gloss finish etc. complete in all respects.																	
59	NS	Providing and fixing first class coloured glazed tiles (of orient/Kajaria make) of size 200x300mm with minimum thickness 5mm in skirting and dado on 12mm thick cement plaster 1:3(1Cement 3Sand) the back of tiles to be buttered with gre (as per approval of Engineer-in-charge)	792.00	Sqm	500.00	396,000.00	792.00												
60	NS	Providing and laying in floor coloured matt finish ceramic tiles of orient/Kajaria make, size 300x300mm (thickness as per manufacture) without warpage laid on 20mm thick cement mortar 1:3(1 cement 3sand) including grouting the joint	180.00	Sqm	600.00	108,000.00	160.00					20.00					12,000.00		

540

7	10.86+10.95(b)+note	1000 Cum	1267.80	340%	5578.32	55783.20	1.00	9.00	0.00	50204.88	0.00	0.00
	Cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work for wall exceeding 20cm thickness (straight and curved) beams, girders, stair, columns (square or rectangular) battens and lintels etc. excluding steel reinforcement but including centring and shuttering, laid in position complete in all											
a)	1st storey	600.00	Cum		5571.46	3582976.00	398.00	202.00	0.00	1206234.92	0.00	0.00
b)	1st storey	350.00	Cum		6003.58	2101253.00	250.00	100.00	0.00	600358.00	0.00	0.00
c)	1st storey	20.00	Cum		6035.70	120714.00	17.00	3.00	0.00	18107.10	0.00	0.00
8	10.114	140.00	Sqm		154.22	2.590.80	110.00	30.00	0.00	4626.60	0.00	0.00
	Damp proof course 40mm thick if cement concrete 1:2:4 using stone aggregate 20mm nominal size with 2 coats of bitumen 20/30 penetration at 1.65kg per sqm. laid hot and sanded.											
9	10.132	150.00	Cum		2826.56	423964.00	85.00	65.00	0.00	183726.40	0.00	0.00
	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in pavement, roads, taxi-tracks and run ways, laid to required slope and camber, i/c consolidation, finishing and tamping											
10	11.2	290.00	Cum		1967.25	570502.50	155.00	135.00	0.00	265578.75	0.00	0.00
	First class brickwork laid in cement sand mortar 1:6 in foundation and plinth.											
11	11.7											
	First class brickwork laid in cement sand mortar 1:6 in first storey upto 4 meter above plinth level.											
(i)	-do- (first storey)	208.00	Cum		2072.25	431028.00	245.00	0.00	37.00	0.00	76673.2	0.00
(ii)	11.7+11.4(i)	215.00	Cum		2113.50	454402.50	245.00	0.00	30.00	0.00	63405.0	0.00
(iii)	11.7+11.4(i)	60.00	Cum		2154.75	129285.00	155.00	0.00	95.00	0.00	204701.2	0.00
12	11.48(a)											
	11.4' cm thick brick wall laid in cement sand mortar 1:4 in superstructure.											
(i)	-do- (first storey)	905.00	Sqm		275.50	249327.50	670.00	235.00	0.00	64742.50	0.00	0.00
(ii)	-do- (second storey)	753.00	Sqm		280.25	211028.25	790.00	0.00	37.00	0.00	10369.2	0.00

- 43 -

14	13.44(a)	Providing and laying 100mm dia H.C.I. pipe I.S.I. mark including drilling joints with lead and spun yarn etc. complete fixed in position under floors.	2210.00 180.00	Mtr.	53.95 93.05	400% 350%	239.75 418.73	596147.50 75270.50	1640.00 0.00	570.00 180.00	0.00 0.00	153757.50 75370.50	0.00 0.00
15	13.46(a)	Extra over rate of item Nos. 13.43 and 13.45(a) in case lead joints are used instead of cement joints.	230.00	per joint	24.30	350%	109.35	75370.50	0.00	230.00	0.00	25150.50	0.00
16	13.49	Providing and fixing C.I plain bends in position with gutter etc.										0.00	0.00
17	13.50	For 100mm dia Top Khurra 0.6x0.6m for rain water pipe in 25mm thick cement concrete 1:2:4 over 50 mm thick cement concrete 1:8:16.	40.00 20.00	Each Each	57.45 12.30	350% 200%	258.53 36.90	10341.00 738.00	0.00 20.00	40.00 0.00	0.00 0.00	10341.00 0.00	0.00 0.00
18	13.62	Providing and laying four courses of water proofing treatment consisting of first and third course of blown type bitumen grade 85/25 applied hot at 1.6 Kg per sqm for each course and second course of fibre glass R.P tissue and fourth and final course of stone grit 6mm and down size or pea sized frit spread at 0.006 cum per Sqm including preparation of surface.	220.00	Sqm	31.00	200%	93.00	20460.00	0.00	220.00	0.00	20460.00	0.00
19	13.66	Providing and laying cinder concrete in cement 1:15(1 cement and 15 cinder)on terraced roofs & (1st storey) laid to slope including consolidating the same.										0.00	0.00
20	14.1-10 26 Based derived rate	-do second storey Sand filling under floor i/c laying consolidation, compaction & watering etc.	46.00 3806	Cum Cum	214.65 69.30	200% 340%	643.95 304.92	29621.70 1160525.52	10.00 2820.00	6.00 986.00	0.00 0.00	3863.70 300651.12	0.00 0.00

21		use of 10mm thick cement concrete 1:8:16 and 100mm sand or stone filling	Sqm	6.95	0%	62.56	1.94	393	0.00	638	0
22	14.3	Floating coat of 150mm thick neat cement laid in one operation to the topping	420	Sqm	3.70	340%	16.28	6837.60	0.00	70.00	0.00
23	14.4	Scored of 50mm thick cement concrete 1:8:16 to be laid below the topping.									1139.6
		-do- (second storey)	1343	Sqm	15.65	340%	68.86	92478.98	0.00	107.00	0.00
		-do- (third storey)	10		15.95	340%	70.18	701.80	0.00	0.00	0.00
24	14.10	Conglomerate floor 50mm thick cement concrete topping 1:2:4									736
		-do- (First storey)	610	Sqm	37.60	340%	165.44	100918.40	112.00	0.00	18529.28
		-do- (second storey)	210	Sqm	37.90	340%	166.76	35019.60	210.00	0.00	35019.60
25	14.49	Marble stone flooring 20mm to 25mm thick slab including matching grains of marble laid in any pattern as specified over base of 12mm thick cement coarse sand mortar 1:3 and jointed with white cement slurry mixed with pigment to match the shade of marble including rubbing and polishing (Third quality)									0.00
	(a) iii	-do- (First storey)	273		478.60	90%	909.34	248249.82	273.00	0.00	248249.82
	(a) iii + note (i)	-do- (second storey)	273		478.90	90%	909.91	248405.43	273.00	0.00	248405.43
26	14.62	Kotah stone flooring 34mm to 40mm thick in any pattern as specified over 12 mm thick base of cement coarse sand mortar 1:3 laid and jointed with neat cement slurry mixed with pigment to match the shade of stone including rubbing and polishing									0
	+note(i)	-do- (First storey)	350	Sqm	201.95	200%	605.85	2117047.50	350.00	0.00	212047.50
	+note(i)	-do- (second storey)	350	Sqm	202.25	200%	606.75	212362.50	350.00	0.00	212362.50
	+note(i)	-do- (third storey)	10	Sqm	202.55	200%	607.65	6076.50	10.00	0.00	6076.50
27	14.66	Kotah stone 20mm thick in skirting of steps, dados pillars and wall facing in any pattern as specified 12mm thick cement coarse sand plaster 1:3 laid and jointed with neat cement slurry mixed with pigment to match the shade of stone including rubbing and polishing including labour for mixing cramps, dowels and pins etc.									0
	+note(i)	-do- (First storey)	36	Sqm	237.00	200%	711.00	25596.00	36.00	0.00	25596.00
	+note(i)	-do- (second storey)	36	Sqm	237.30	200%	711.90	25628.40	36.00	0.00	25628.40

18	15.5	(i)	(third)	12mm thick cement plaster 1:4	Sqm	37.60	100%	712.8	32.00	0.00	1000.00	0.00	0.00
	+note(i)			-do- (First storey)	1850	Sqm	12.70	340%	55.88	103378.00	2100.00	0.00	1397.0
	+note(i)			-do- (second storey)	1714	Sqm	12.88	340%	56.67	97135.81	1900.00	0.00	1054.0
	+note(i)			-do- (third storey)	105		3.06	340%	57.45	6033.72	650.00	0.00	3131.7
29	15.10			15mm thick cement plaster 1:4 on the rough side of single or half brick								0.00	0.00
	15.10+note			-do- (First storey)	1850.00	Sqm	15.65	340%	63.86	127391.00	1850.00	0.00	0.00
	15.10+note			-do- (second storey)	1650.00	Sqm	15.83	340%	69.65	114925.80	1650.00	0.00	0.00
	15.10+note			-do- (third storey)	105.00	Sqm	16.01	340%	70.44	7396.62	800.00	0.00	48958.0
30	15.18			Rough cast exterior cement plaster on walls with a mixture of sand and gravel or crushed stone graded from 2.36mm to 12mm nominal size dashed over and including fresh plaster with cement mortar 1:3 (cement & sand) mixed with 10% finely ground hydrated lime by volume of rounded angles not exceeding 80mm in girth.								0.00	0.00
	+note i			-do- (First storey)	1400.00	Sqm	35.40	340%	155.76	218064.00	0.00	1400.00	218064.00
	+note i			-do- (second storey)	1400.00	Sqm	35.58	340%	156.55	219172.80	0.00	1400.00	219172.80
	+note i			-do- (third storey)	205.00	Sqm	35.76	340%	157.34	32255.52	0.00	205.00	32255.52
31	15.52			10mm thick cement plaster 1:4								0.00	0.00
	15.52+note 1			-do- (First storey)	1343.00	Sqm	12.65	340%	55.66	74751.38	2000.00	0.00	657.00
	15.52+note 1			-do- (second storey)	1343.00	Sqm	12.83	340%	56.45	75815.04	2220.00	0.00	877.00
	15.52+note 1			-do- (third storey)	108.00	Sqm	13.01	340%	57.24	6182.35	200.00	0.00	92.00
32	15.77			20mm thick cement plaster damp proof course 1:3 with 2 coats of bitumen at 1.65 Kg per sqm laid hot and sanded:-								0.00	0.00
	(a)			Vertical (do second storey)	150.00	Sqm	30.88	340%	135.87	20390.80	150.00	0.00	0.00
	(b)			Horizontal (do second storey)	120.00		29.13	340%	128.17	15580.64	125.00	0.00	5.00
33	15.30			Extra for lining out in rough-h cast pebble cement plaster and terrazzo finish surfaces finished.	2800.00	Sqm	3.30	340%	14.52	40656.00	3000.00	0.00	200.00
34	16.1			Preparation of plywood surface for painting including sand papering the surface and applying with approved quality filler consisting of white lead, linseed oil, varnish and talk mitt including finishing the surface to required finish complete (with first quality material)	450.00	Sqm.	4.60	125%	10.35	4657.50	590.00	0.00	140.00

5-66-

35	36	37	38	39	40	41	42	43	C)	44	C)	i)	ii)
Aluminum priming coat on wood work including preparation of surface knotting and stopping etc. (with 1st quality paint)	Aluminum priming coat on wood work including preparation of surface knotting and stopping etc. (with 1st quality paint)	Aluminum priming coat on metal primer on new steel or iron work including preparation of surface with first quality paint)	Painting two coats with ready mixed paint for metallic surfaces in all shades on old steel or iron work.	Painting two coats with ready mixed exterior paint in all shades on newly plastered or concrete surface of wall.	White wash three coats	Preparation of plastered surfaces for oil bound distemper including sand papering the surface, applying 1 coat of linseed oil and filling with approved quality filler consisting of white lead, linseed oil, varnish and chalk mists including finishing the surface to the required finish complete.	Distemping with washable oil bound distemper (of approved manufacture) two coats over one priming coat on new work.	Supply and fixing hydraulic door closer, I.S.I. mark with necessary screws, etc. complete	I.S.I. designation No. II (size of door 801 mm to 1000mm)	Providing and fixing sliding bolt with nuts and screws etc. complete	Iron	Size 300mmx16mm	Size 250x16 mm
16.3	16.3	16.9	16.18	16.26	16.48	16.52	16.58	17.82	C)	17.83	C)	i)	ii)
450.00	450.00	960.00	960.00	2150.00	2800.00	5860.00	5860.00	36.00	36.00	50.00	100.00	50.00	100.00
Sqm.	Sqm.	Sqm.	Sqm.	Sqm.	Sqm.	Sqm.	Sqm.	Each	Each	Each	Each	Each	Each
9.40	9.40	3.15	7.00	13.45	1.25	11.15	9.10	216.50	216.50	17.45	16.35	17.45	16.35
125%	125%	125%	125%	125%	125%	125%	125%	250%	250%	250%	250%	250%	250%
21.15	21.15	7.09	15.75	30.26	2.81	25.09	20.48	757.75	757.75	61.08	57.23	61.08	57.23
9517.50	9517.50	6804.00	15120.00	65064.38	7875.00	147012.75	119982.50	27279.00	27279.00	3053.75	5722.50	3053.75	5722.50
700.00	700.00	220.00	100.00	0.00	2800.00	9860.00	9860.00	36.00	36.00	25.00	85.00	25.00	85.00
0.00	0.00	740.00	860.00	2150.00	0.00	0.00	0.00	0.00	0.00	25.00	15.00	25.00	15.00
250.00	250.00	0.00	0.00	0.00	0.00	4000.00	4000.00	0.00	0.00	0.00	0.00	0.00	0.00
0.00	0.00	5244.75	13545.00	65064.38	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1526.88	858.38
523	523					100350	81900						

547

1 of fittings, complete
for doors and windows such as
tower bolts, handels etc. and
screws for these fittings
(excluding sliding bolts)

	a)	For single leaf shutter	280.00	Sqm	6.40	25%	22.40	6272.00	280.00	0.00	0.00	0.00
	b)	For double leaf shutter	142.00	Sqm	10.15	250%	35.13	5044.55	142.00	0.00	0.00	0.00
46	17.87	Providing and fixing 0.50 mm thick aluminium sheet including cost of necessary screws etc complete-	50.00	Sqm	30.5	250%	316.93	15046.25	50.00	0.00	0.00	0.00
47	17.93(a)iii note(i) of 17.18	Factory manufactured solid flush door shutters with block board core as per I.S typephenol formaldehyde synthetic resin hot pressed, conforming to I.S 2202 part I and II, fixed position including iron hinges, screws, chocks/ cleats and stops, etc(excluding the cost of any fittings other than specified above , but including labour for fixing the same in position):-										
	a) iii	35mm thick	213.00	Sqm	436.15	150%	1090.38	308576.13	195.00	88.00	0.00	95953.00
48	17.90 (b)	Factory manufactured panelled door or glazed window shutter of commercial hard wood such as hollock, champ, chikrassy and chaplash etc. (non- confireous timber other than teak conforming to I.S. specification no. 1003 kiln seasoned) with 100mm wide vertical styles, 150mm wide lock rail, 200mm wide bottom rail & 100mm wide others rail with panelles of 15mm thick, tongued and grooved of commercial hard wood i/c the cost of iron hinges, screws, chocks/cleats, stops, nails etc. complete fixed in position excluding the cost of any fittings other than specified above but including the labour for fixing the same in position										0.00
	b)	Glazed shutter (35 thick)	150.00		424.15	250%	1484.53	222678.75	115.00	35.00	0.00	51958.38

618-

4	12	rough and steel (using angles, flats, square bars, tees and channels) ladders; grills, grating frames, window guard iron doors operable of fixed staircase of parapet or any other type of railing, gates and tree guards etc including cost of screws and welding rods or bolts and nuts complete fixed in position.	0.00	1040	325	442	578	37.00	0.00	30000.48	55504						
50	18.22	Cold twisted deformed (ribbed/tor steel) bars for RCC works where not including bending, binding and placing in position complete.	2515.00	Qd.	917.05	350%	4126.73	10378713.38	3860.00	0.00	1345.00	0.00	220702.50	0.00	3328.56	0.00	3112
51	18.30	S/F glass panes including special metal sash putty of approved make										0.00					
(b)		Glass panes 4mm thick, exceeding 40 sq.dm.area	580.00	Sqm	115.40	325%	490.45	284461.00	130.00	450.00	0.00						
52	18.34(a)	Pressed steel sheet frames (chowkhats), consisting of 2mm thick steel sheet of the specified section, including iron lugs (hold fasts), iron hinges, conforming to P.W.D. specifications including bolts for fixing stops, lock notch provision for receiving tower bolts and finished with one coat of ready mixed paint red lead non-setting primer of approved quality fixed in position including the cost of cement concrete 1:3:6 for filling in the frame and cement concrete 1:3:6 for lugs complete:-															
(a)		Door and window frame of size 89 x 50mm with 40mm wide single rebate	2203.00	Mtr.	71.55	325%	304.09	669904.76	2120.00	83.00	0.00						
53	6.2 C(iii)	Earth work in excavation in ordinary soil exclusive of compensation of earth-Lead															
		Extra for every 7.5 mtrs additional lead beyond 300mtrs by upto 495 mtrs by animal or by animal-driven-cart.	0.00	100 Cum	7.96	350%	35.82	0.00	3328.56	0.00	3328.56	0.00					

-49-

54	10.86+ note (v) b	Cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work for wall exceeding 20cm thickness (straight beams, girders, stair, curved columns (square or rectangular) batters and lintels etc. excluding steel reinforcement but including centring and shuttering, laid in position complete in all directions)	0.00	Cum	1116.45	340%	4912.38	0.00	35.00	0.00	35.00	0.00	17193
55	13.89	Providing & fixing PVC Rain Water pipe 6 kg pressure of ISI mark in cement mortar durability masonry work.										0.00	
(b)		150 MM dia PVC pipe 6kg. Pressure	0.00	Mtr.	336.65	0%	336.65	0.00	200.00	0.00	200.00	0.00	6733
56	13.90	Providing fixing PVC bend ISI mark.										0.00	
(b)		150 mm dia PVC bend	0.00	Each	165.40	0%	165.40	0.00	40.00	0.00	40.00	0.00	661
57	16.25	Applying priming coat with cement primer in all shades on newly plastered or concrete exterior surfaces.	0.00	Sqm	4.15	125%	9.34	0.00	14200.00	0.00	14200.00	0.00	13209
58	16.79 (b)	Providing two coats of exterior acrylic emulsion paint										0.00	
(b)		1st quality	0.00	Sqm	48.75	0%	48.75	0.00	3010.00	0.00	3010.00	0.00	14673
59	15.15	20 mm thick cement plaster 1:4 in 2 coats work 1st storey		Sqm	20.15	340%	88.66	0.00	1300.00	0.00	1300.00	0.00	11525
		2nd storey	0.00	Sqm	20.33	340%	89.45	0.00	1300.00	0.00	1300.00	0.00	1628
		3rd storey	0.00	Sqm	20.51	340%	90.24	0.00	830.00	0.00	830.00	0.00	7490
60	13.93	Providing & fixing false ceiling with grooves with 12mm to 15mm thick 600mm x 600mm best quality mineral perforated fibre tiles of approved make (Armstrong) fixed on N.S steel runners frames i/c cost of screws, angles, cleats, rowel plus i/c hangers with tapping and painting etc complete in all respect as per approval of Engineer-in- Charge. (Rate including ceiling premium)	0.00	Sqm	800.00	0%	800.00	0.00	2200.00	0.00	2200.00	0.00	176000

—SD—

61	17.97	providing and fixing 22 mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS : 12813 grade I type II in panelling fixed in aluminium doors windows shutters and partition frames with C.P.brass/stainless steel screws etc. complete	0.00	Sqm	745.65	0%	745.65	0.00	45.00	0.00	45.00	0.00	33.15
62	13.64	Pre-laminated particle board with decorative lamination on one side & balancing lamination on both side. Cement concrete 1:2:4 gola 10cmx10cm quadrant along junction of roof with parapet wall finished smooth where specially specified.FR=5.35	0.00	Mtr.	5.35	200%	16.05	0.00	350.00	0.00	350.00	0.00	5.11
Total:			34987453.04			6900820.77			354502.77			-335579.555044	

Difference in all items except steel
 Difference in steel item
 Add contractor premium @ 24.50% on all items except steel 18.22
 Add contractor premium @ 33.25% on steel item i.e. 18.22
 Total Difference including contractor premium
 Total Difference in NS items Civil
 Total difference in Civil items
 Saving in Public Health Schedule
 Saving in Public Health Non Schedule
 Already approved agreement amount including civil, PH & EI
 Total Amount to be approved
 Total Enhancement amount
 Total Percentage of Enhancement

-----Sd-----
 EXECUTIVE ENGINEER
 Construction Cell
 NIT-Kurukshetra

-5/-

Item No. 14.5 To consider & approve the item(s) of work for the construction of Extension Block of Guest House Building at NIT, Kurukshetra.

The B & WC in it's 11th meeting held on 28.07.2009 approved the revised cost estimate of Rs. 181.27 lac for the construction of extension block of Guest House building at NIT, Kurukshetra. As this building will be used by V.V.I.P's during their stay at NIT, Kurukshetra, to have a better look of rooms & to facilitate more comforts to the Guests, it is desired that the false ceiling should be provided in all rooms and dinning hall of this building where as this item of work was not included in the preliminary estimate earlier. Accordingly, a cost estimate amounting to Rs. 5.94 lac has been framed and scrutinized by the construction cell to cover the cost of this additional item. The expenditure to be incurred on this additional item of work is Rs. 5.94 lac. The additional amount of Rs. 5.94 lac will be met out within the already approved amount of Rs. 181.27 lac.

The B & WC may kindly consider and approve this item of work i.e. false ceiling for Rs. 5.94 lac within the already approved amount of Rs. 181.27 lac for this work.

Sr. No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Total Rate	Estimated Cost	Qty. likely to be Executed	Qty. in Bill
SUB PART-III: INTERNAL PH SERVICES (SCHEDULE ITEMS)										
	30.3	Providing and fixing in position best Indian make Anglo Indian water closet suit (as approved by the engineer-in-charge) consisting of:								
	i)	Wash down closet set vitreous china ware (to the approval of the engineer-in-charge) with 'P' or S trap with or without vent as required and suitable joint for closet inlet;								
	ii)	One piece seat and lid in hollow black or white plastic fitted with chromium plated brass hinges and rubber buffers; (to the approval of the engineer-in-charge)								
	iii)	12.5 litres capacity mosquito proof C.I flushing cistern of best Indian make and all other necessary fittings complete as fully described in item no. 30.1 above								
	iv)	32mm diameter telescopic 1.25 mm thick galvanized inside and outside steel flush pipe with clips.								
		Complete in all respects including cutting and making good the walls and floors and painting of fittings etc.								
		Single colour	20	Each	1474	250%	5159	103180	0	20
	30.13	Extra over item No. 30.3 to 30.6 for providing and fixing best Indian make plastic hygienic seat with lid complete instead of hollow black or white plastic seat and lid								
	(iii)	Coloured plastic seat other than black or white (solid)	20		251	250%	878.5	17570	17	3
	30.40	Providing & fixing 25mm thick, marble partitions for different type of urinals.								
	(b)	Vitreous Chinaware partition plate.	2	Each	434.00	250%	1519.00	3038	0	2
	30.41	P/F in position best Indian make lavatory Suits								
		White								
		(iv) Size 550mmx400mm with one no. tap	0	Each	407.00	250%	1424.50	0	19	0
		Single colour								
		(iv) Size 550mmx400mm with one no. tap	20	Each	521.00	250%	1424.50	28490	0	20
5	30.45	Providing and fixing in position best Indian make chromium plated brass 2nd tap for lavatory suite.	20	Each	92.00	250%	322.00	6440	19	1
	30.48	P/F in position 32mm diameter G.I. waste pipe embedded in wall	20	Each	98.00	250%	343.00	6860	20	0
	30.50	P/F in position best Indian make C.P. brass bottle traps 32mm diameter	20	Each	92.00	250%	322.00	6440	20	0
6	30.58	Providing and fixing in position best quality stainless steel draining board with iron brackets for building into wall including painting, cutting and making good the walls etc.								
		Size 600 mm x 450 mm	1	Each	1774.00	250%	6209.00	6209	0	1
	30.62	P/F 40mm diameter G.I. waste pipe embedded in wall or upto floor level including cost of union and plumbing joints	18	Each	118.00	250%	413.00	7434	3	15
8	30.66	P/F in position best Indian make showers with 15mm diameter inlet.								
	C)	C.P. brass with revolving joint.	20	Each	123.00	350%	553.50	11070	17	3
9	30.67	P/F in position best Indian make paper holder fixed into C.P. including cutting & making good the walls etc.								
	(a)	C.P. brass	20	Each	27.50	250%	96.25	1925	17	3
10	30.68	Providing and fixing in position best Indian make towel rails fixed including cutting and making good the wall etc.								
	(b)	20 mm diameter C.P. brass adjustable								

No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Total Rate	Estimated Cost	Qty. already to be Executed	Qty. remaining
SUB PART-III: INTERNAL PH SERVICES (SCHEDULE ITEMS)										
		(i) 750 mm long	20	Each	65.00	250%	227.50	4550	19	1
		(ii) 600 mm long	30	Each	57.00	250%	199.50	5985	19	11
11	30.69	P/F in position glass shelf fixed in with rawl plugs with C.P. brass screws complete including cutting & making good the walls etc.								
	(a)	With C.P. brass bracket and guard rail								
		(i) 600mm x 125mm	20	Each	72.50	250%	253.75	5075	19	1
	30.70	P/F in position best Indian make soap dish fixed into wall with C.P. brass screws complete in all respects including cutting & making good the walls etc.								
	(a)	C.P. brass								
	(i)	Soap dish large	20	Each	59.00	250%	206.50	4130	20	0
13	30.71	P/F in position best Indian make bevelled edge 5.5mm thick mirror fixed in position by means of 4 nos. C.P. brass screws and washers complete including cutting and making good the walls etc.								0
	(a)	Indian make								
		(ii) 600 mm x 450mm	20	Each	107.00	250%	374.50	7490	20	0
14	30.73	P/F in position best Indian make coat & hat hooks fixed with C.P. brass screws complete including cutting and making good the walls etc.								
	(a)	C.P. brass								
		(ii) Two way	68	Each	43.00	250%	150.50	10234	68	0
	30.74	Providing and fixing in position super quality 65 mm i/d opening CP brass dome type hinged grating weighting about 750 gms. Fixed in cement mortar 1:2 complete in all respects (as required by the Engineer-in-charge).	38	Each	67.50	250%	236.25	8978	38	0
16	30.75	Providing & fixing in position 15mm i/d C.P. brass bib cocks of best quality (as required by the Engineer-in-charge)								
	(a)	Bib cock long body	70	Each	116.00	250%	406.00	28420	60	10
	(c)	Bib cocks	38	Each	100.00	250%	350.00	13300	20	18
	30.76	P/F in position C.P. brass stop cocks (as approved by Engineer-in-charge)								
	(a)	15mm stop cocks								
		(ii) Concealed stop cocks with flange	140	Each	130.00	250%	455.00	63700	52	88
	30.8	Extra over item Nos. 30.1 to 30.4 and 30.6 for providing and fixing 15 litres capacity vitreous China high level cistern complete with internal brass fitting instead of 12.5 litres capacity high level C.I cistern complete (as approved by the engineer-in-charge)								
	(i)	White	0	Each	319.00	250%	1116.50	0	17	0
	(ii)	Single colour	20	Each	458.00	250%	1603.00	32060	0	20
19	30.83	P/F in position best Indian make C.P. brass inlet connection 15mm with 375mm pipe & CP brass nuts.	120	Each	115.00	250%	402.50	48300	100	20
	30.84	P/F in position HCl soil, waste, vent pipes to ISI specification or any other reputed firm including cutting & wastage etc. & cutting holes in walls, roofs or floor etc. and making good the floor & wall but excluding cost of painting								
	(a)	100mm internal diameter	300	Mtr.	97.50	300%	390.00	117000	240	60
	(b)	75mm internal diameter	300	Mtr.	83.00	300%	332.00	99600	215	85
	30.87	Providing lead caulked joints to HCl pipes & specials conforming to ISI specification of ELC or any other reputed firm including cost of lead varn. fuel & tools etc.								
	(a)	100mm internal diameter (1.13 kg)	195	Each	33.50	225%	108.88	21231	225	0
	(b)	75 mm internal diameter (0.91 kg)	300	Each	27.50	225%	89.38	26813	230	70

Sl. No.	HSR No.	QTY	UNIT	Rate	30%	50%	60%	70%	80%	90%	Executed	
SUB PART-III: INTERNAL PH SERVICES (SCHEDULE ITEMS)												
22	30.88	Providing and fixing in position MS or Heavy flat iron clamps inside out of MS flat not less than 5 mm of the approved design for fixing CI Soil waste vent or anti pipes to walls complete in all respects including cutting and making good the walls and floors etc. and painting										
	(a)	For 100 mm internal diameter pipes	120	Each	12.50	300%	50.00	6000	50	70		
	(b)	For 75 mm internal diameter pipes	120	Each	11.00	300%	44.00	5280	50	70		
23	30.89	P/F HCl floor trap ISI marked of the self-cleaning design with C.P. brass hinged grating with or without vent arm & including cement concrete 1:2:4 complete in all respects										
	(b)	With 75mm internal diameter outlet	38	Each	105.00	300%	420.00	15960	30			
24	30.90	PROVIDING AND FIXING IN POSITION HCl 50mm INTERNAL DIAMETER OUTLET PLAIN NAHAN TRAP ISI Marked of the self cleaning design with CP BRASS HINGED GRATING WITH FRAME WEIGHING 6.80 KG EACH FIXED complete as fully described in item no. 30.89 above.										
	(b)	75 mm I/d outlet plain Nahani Trap.	38	Each	100.00	300%	400.00	15200	4	3		
25	30.91	P/F In position HCl specials for soil waste vent pipes to ISI specification including cutting holes in walls & making good but excluding cost of lead joints										
	(a)	For 100mm internal diameter pipes										
		(i) heel rest bend	20	Each	58.00	300%	232.00	4640	16			
		(ii) Double junction with door 100 mm x100x100x100mm,	20	Each	99.00	300%	346.00	6920	0	2		
		(iv) single junction with door 100mm x100mm x100mm	18	Each	86.50	300%	346.00	6228	16			
		(vi) Single junction plain 100mmx100mmx100mm	20	Each	76.50	300%	306.00	6120	0	20		
		(xiii) Bend with door	10	Each	60.00	300%	240.00	2400	0	10		
		(xiv) Bend plain	10	Each	53.00	300%	212.00	2120	0	10		
		(xv) Terminal guard	17	Each	39.50	300%	158.00	2686	0	1		
		(xvi) Cowls	20	Each	36.50	300%	146.00	2920	16			
		(xxii) Collars	30	Each	27.50	300%	110.00	3300	25			
	(b)	For 75mm internal diameter pipes										
		(i) Heel rest bend	20	Each	39.50	300%	158.00	3160	18			
		(iv) Single junction with door 75mmx75mmx75mm	18	Each	59.00	300%	236.00	4248	31			
		(vi) Single junction plain 75mmx75mmx75mm	19	Each	50.50	300%	306.00	5814	0	1		
		(xiii) Bend with door	17	Each	42.00	300%	168.00	2856	0	1		
		(xiv) Bend plain	2	Each	39.50	300%	158.00	316	0			
		(xv) Terminal guard	17	Each	27.50	300%	110.00	1870	0	1		
		(xvii) Cowls	17	Each	28.00	300%	112.00	1904	18			
		(xviii) Collars	57	Each	22.50	300%	90.00	5130	25	3		
26	30.95	Cutting chase in brick wall in cement for embedding G.I. or HCl pipe lines & making good the same										
	(a)	Size 75x75mm	60	Mtr.	6.00	250%	21.00	1260	60			
27	30.101	Painting HCl soil waste and vent pipes and fittings with black bitumastic ordinary paint of approved manufacture two coats on new work.										
	(a)	100 mm internal diameter	300	MTR	1.85	250%	6.48	1943	150	15		
	(b)	75 mm internal diameter	300	MTR	1.35	250%	4.73	1418	150	15		
28	30.110	P/F In position automatic brass ball valves in tanks										
	(b)	With plastic ball										
	(iii)	25mm diameter	10	each	65.50	250%	229.25	2293	15			

No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Total Rate	Estimated Cost	Executed	
SUB PART-III: INTERNAL PH SERVICES (SCHEDULE ITEMS)										
	30.114	P/F in position Gully traps fixed in cement concrete 1:4:8 with HCl grating 150x150mm CI cover weighing approximately 7.26 kg & frame clear opening 300 x 300mm and chamber including cost of brick work 1:5 cement concrete 1:8:16 and C.C. 1:2:4 in coning								
	(b)	100mm internal diameter HCl gully traps	19	Each	208.00	300%	832.00	15808	17	2
	30.115	Providing and fixing in position best Indian make vitreous china ware channel of size 600 mm x 150 Including laying and fixing in cement concrete 1:2:4 complete as required by the Engineer-in-charge								
	(i)	White	6	Each	92.00	250%	322.00	1932	4	2
	28.24	Cutting holes upto 23cm through brick work in cement wall for pipes and making good								
	(a)	11.43cm thickness of walls	40	Each	14.00	250%	49.00	1950	20	20
	(b)	22.86 cm. thickness of walls	60	Each	20.35	250%	71.23	4274	20	40
	28.47	Bailing out water from the trenches for making new connections in fully charged pipelines								
	(a)	Upto 200mm internal diameter	4	Each	67.50	250%	236.25	945	1	3
	29.84	Constructing brick masonry inspection chamber upto 60 mtr.depth in cement mortar 1:5 cement concrete 1:2:4 benching, 12mm thick cement plaster, RCC 1:2:4 slab 100mm thick with with 455x455 mmx455x610mm inside light duty GI inspection chamber cover & frame with 3 coats of black bitumastic paint.								
	(c)	Size 600x900mm inside	20	Each	690.00	375%	3277.50	65550	12	8
34	29.85	Extra for every 0.30 mts. depths of inspection chamber								
	(c)	600mmx900mm	20	Each	139.00	375%	660.25	12205	5	15
35	6.8	Excavation for pipelines running under pressure in trenches and pits in open areas where disposal of surplus earth is done alongwith the alignment and restoration of unmetalled surface to the original condition								0
	(a)	Without timbering and shoring upto 1.5 meters depth	90	100 Cum	1030.00	300%	4120.00	3708	2	88
36	6.10	Excavation of trenches in street lanes or in open area for storm sewer, sewers running by gravity & man holes to full depth and removal of surplus soil upto to a lead of 1Km in ordinary soil								0
	(a)	For depth of excavation not exceeding 3 mts. below ground level	150	100 Cum	1189.00	300%	4756.00	7134	70	80
37	10.39	Cement concrete 1:4:8 with stone aggregate 40mm nominal size in foundation and plinth	20	Cum	403.10	340%	1773.64	35473	2	18
	10.41	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in foundation and plinth	10	Cum	615.60	340%	2708.64	27086	20	0
	10.59+ note V (b)	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in in first storey upto 4 metres above plinth level								0
		-do- (first storey)	3	Cum	621.85	340%	2736.14	8208	0	0
		-do- (second storey)	4	Cum	624.40	340%	2747.36	10989	0	4
40	30.5 (a) (i)	Providing & fixing in position best Indian make European type water closet suite, syphonic type consisting of								

Sl. No.	NSR No.	Description	Qty.	Unit	Rate	Gr.	Total Rate	Estimated Cost	Executed	
SUB PART-III: INTERNAL PH SERVICES (SCHEDULE ITEMS)										
		(i) Vitreous chinaware syphonic suite with 15 litres capacity matching chinaware cistern complete with 'P' or 'S' trap with or without vent								
	(a)	Single trap syphonic W.C. suites (White)	0	Each	1542.00	250%	5397.00	0	17	0

Sr. No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Rate	Estimated Cost	Qty. Likely to be Executed
SUB PART-IV: INTERNAL PH SERVICES (NON-SCHEDULE ITEMS)									
1		Providing and laying cement concrete 1:2:4 75mm in bed and around C.I soil waste pipe 100mm and 75mm i/d under floor including centering and shuttering where required.							
	(a)	100mm dia	35	Mtr.	300.00		300.00	10500	110.0
	(b)	75 mm dia	60	Mtr.	240.00		240.00	14400	65.0
2	NSR	P/F in position C.P. jet connection of EWC complete including C.P. plate for jet & PVC connection for jet point complete in all respects.	20	Each	600.00		600.00	12000	17.0
3	NSR (based on 30.53)	Providing and fixing in position best quality stainless steel sinks with complete fittings as fully described in item No. 30.51 above.							
	(a)	600 mm x 450 mm x 200 mm	2	Each	9000.00		9000.00	18000	3.0
4	NSR	Providing, laying, jointing glazed stoneware pipes grade A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement, 1 fine sand) including testing of joints etc. complete.							
		150mm i/d	100	Mtr.	150.00		150.00	15000	145.0
	(b)	200mm i/d	50	Mtr.	230.00		230.00	11500	2.0
5	NS	Providing and fixing of G.M. Peat valves heavy patterns with hand wheels ISI marked to GI pipe lines.							
	(a)	25mm i/d	20	Each	400.00		400.00	8000	49.0
	(b)	40mm i/d	10	Each	850.00		850.00	8500	3.0
	(c)	80mm i/d	1	Each	1600.00		1600.00	1600	0.0
6	NS	Providing, testing and fixing G.I. pipe 'B' class medium duty including cost of specials such as Tee, elbow, bends etc. and threading inside the building							
		15mm i/d	400	Mtr.	120.00		120.00	48000	300.0
		20mm i/d	250	Mtr.	144.00		144.00	36000	400.0
		25mm i/d	200	Mtr.	190.00		190.00	38000	55.0
		40mm i/d	100	Mtr.	250.00		250.00	25000	25.0
		50mm i/d	100	Mtr.	300.00		300.00	30000	100.0
		80mm i/d	50	Mtr.	500.00		500.00	25000	2.0
7	NS	Extra for providing and fixing union coupling to G.I. pipe lines including cost of union complete							
		15mm i/d	40	each	50.00		50.00	2000	2.0
		20mm i/d	25	each	78.00		78.00	1950	55.0
		25mm i/d	20	each	100.00		100.00	2000	2.0
		40mm i/d	10	each	180.00		180.00	1800	2.0
		50mm i/d	10	each	200.00		200.00	2000	5.0
		80mm i/d	5	each	288.00		288.00	1440	0.0
	NS	Providing and stringing S & S centrifugally cast (spun) iron pipes (Class LA) complete in trenches to the approval of Engineer-in-charge.							
		80mm i/d	50	Mtr.	925.00		925.00	46250	1.0

Sr. No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Rate	Estimated Cost	Qty. Likely to be Executed
9	NS	Supplying and fixing ISI marked sluice valve double flanged with brass spindle complete in all respect to the approval of Engineer-in-charge. 80 mm	2	Each	3000.00		3000.00	6000	0.00
10	NS	Const. of sluice valve haudi 1m x 1m x 1m with brick work 1:5 cement sand mortar finished with 12.5mm cement plaster 1:4 including RCC 1:2:4 slab with reinforcement, surface box complete in all respect to the approval of Engineer-in-charge.	2	Each	3000.00		3000.00	6000	0.00
11	NS	Providing and fixing in position H.D.P.E. water tanks complete with inlet, outlet, scour and overflow flanges including masonry based underneath as approved by the Engineer-in-charge of different capacity tanks complete in all respect.							
		Capacity upto 2000 litres	20000	Ltrs.	7.00		7.00	140000	20000.00
	NS	Making sewer connection with the existing sewer line	4	Each	1000.00		1000.00	4000	2.00
	1)	All china ware should be of Cera /Hindustan/ CERA/HINDWARE/ PERPYWARE Make Ist quality							
	2)	All C.P. fittings/fixture should be of SEIKO/Parko/ make.							
	3)	All fitting should be Unik & G.I. pipe should be TATA / Jindal Hisar.							

Sl. No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Rate	Estimated Cost	Rate	Amount	Qty. likely to be Executed
		SUB PART-I: INTERNAL CIVIL WORKS (NON SCHEDULE ITEMS)									
		The rate quoted by the contractor shall be for all heights and levels as per drawings and for all scaffolding work and other connecting operations for below mentioned items.									
1.NS		Providing and fixing in position stainless steel Hand Rail system including mid rails welded built-up section using pipes and connecting plates of stainless steel grade 304 polished to satin finish, of required diameter and thickness including cutting, welding, grinding, bending to required profile and shape, hoisting, buffing, polishing, cutting chases/embedding in RCC/masonry, fixing with stainless steel (grade 304) screws, nuts, bolts, rosette covers and washers or stainless steel fasteners to make it rigidly fixed and stable against impact force with necessary bends and terminations and making good the walls / plaster etc. all complete as per drawings and direction of Engineer-in-Charge.									
		The item includes epoxy grouts welding etc. which shall not be measured for purpose of payment. Weight of stainless steel pipes, balusters and mid rails, stainless steel plates, rosette cover, nut and bolts etc as actually provided shall only be measured in Kg. for payment.	500	kg	715.5		715.5	357750.00	615	307500.00	400.00
2.NS		Providing and fixing Aluminum Anodized sliding bolts (ISI marked) necessary stainless steel and make with nuts and screws etc. complete :									
		250x16 mm	80	No.	150.00		150.00	12000.00	125.00	10000.00	20.00
3.NS		Providing and fixing Aluminum Anodized tower bolts of (ISI marked) stainless steel make with necessary screws etc. complete :									
		250x10 mm	100	No.	90.00		90.00	9000.00	80.00	8000.00	20.00
		150x10 mm	100	No.	80.00		80.00	8000.00	70.00	7000.00	20.00
4.NS		Providing and fixing Aluminum Anodized handles (ISI mark) with necessary screws etc. complete.									
		125 mm	200	No.	50.00		50.00	10000.00	45.00	9000.00	100.00
5.NS		Providing and fixing Aluminum hanging floor door stopper of approved make and quality (ACME/BOLT/HARDWYN) with necessary screws etc. complete.									
		Twin rubber stopper.	60	Nos.	40.00		40.00	2400.00	35.00	2100.00	10.00
6.NS		Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing and panelling to be paid for separately) :									
a		For fixed portion.									

Sl. No.	HSR No.	Description	Qty.	Unit	Rate	C.P.	Rate	Estimated Cost	Rate	Estimated Cost	Rate	Estimated Cost
		SUB PART-I: INTERNAL CIVIL WORKS (NON SCHEDULE ITEMS)										
		Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron)	200	kg	290.45		290.45	58090.00	290	58000.00		150.00
	b	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of PVC / neoprene gasket required (Fittings shall be paid for separately).										
		Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron)	200	kg	310.45		310.45	62090.00	300	60000.00		150.00
	NS	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap heading shall be paid in basic item):										
		With float glass panes of 5.50 mm thickness	50	sqm	673.55		673.55	33677.50	600.00	30000.00		50.00
	8. NS	Providing and fixing double action hydraulic floor spring of approved brand and manufacture IS : 6315 marked, for doors including cost of cutting floors as required, embedding in floors and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge.										
		With stainless steel cover plate	2	nos	1733.50	each	1733.50	3467.00	1700.00	3400.00		2.00
	NS	Providing and fixing mirror polish, machine cut granite flooring at stair case, external concourse entrance steps and internal concourse etc., (sample of granite shall be approved by Engineer in-charge) over 20 mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and joints treated with white cement, mixed with matching pigment, epoxy touch ups including rubbing, moulding etc. complete. as per direction of Engineer-in-charge.										
		20 mm thick Granite of any colour and shade as approved by the engineer-in-charge.										
		Any size	100	sqm	3663.00	sqm	3663.00	366300.00	3400.00	340000.00		615.00
	10. NS	Providing and fixing 18 mm thick mirror polished, machine cut granite stone in risers of steps. Skirting, dado and pillars laid on 12mm (average) thick cement mortar 1:3 (1 cement : 3 coarse sand) and joint treated with white cement slurry mixed with pigment to match the shade of the slab including rubbing, curring etc complete at all levels to the satisfaction of Engineer-in-charge.										
		Granite of any colour and shade as approved by the engineer-in-charge.										
	NS	Any size	15	sqm	2889	sqm	2889	43335.00	3000	45000.00		25.00
	11. NS	Providing and laying polished vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:3 (1 cement : 3 coarse sand) including grouting the joints with white cement and matching pigments etc., complete.(Make as per engineer in-charge.)										
	NS	Size of Tile 60x60 cm	215	sqm	1000.00	sqm	1000.00	915000.00	825.00	754875.00		680.00

Sl. No	BSR No.	Description	Qty.	Unit	Rate	C.P.	Rate	Estimated Cost	Rate	Amount	Qty. Likely to be Executed
		SUB PART-I: INTERNAL CIVIL WORKS (NON SCHEDULE ITEMS)									
12. NS		Providing and fixing 18 mm thick mirror polished, machine cut for Kitchen platforms, vanity counters facias and similar locations of required size of approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 with joints treated with									
		Granite stone	35	sqm	3000.00		3000.00	105000.00	3000.00	105000.00	35.00
13. NS		Extra for providing edge moulding to granite stone counters including machine polishing to edge to give high gloss finish etc. Complete in all respects	40	Mtr.	150.00		150.00	6000.00	150.00	6000.00	250.00
14. NS		Providing and fixing first class plain coloured glazed tiles with border and highliter (of orient/Johnson make) of size 300x450 mm with minimum thickness 5mm in skirting and dado on 12mm thick cement plaster 1:3 (1 cement:3 coarse sand) the back of the tiles to be buttered with gre(as per engineer in-charge)	430	Sqm.	650.00		650.00	279500.00	600.00	258000.00	480.00
15. NS		Providing and laying in floor plain coloured matt finish ceramic tiles of orient/Johnson make, size 400mm x 400mm (thickness as per manufacture) without warpage, laid on 20mm thick cement mortar 1:3 (1 cement: 3 coarse sand) including grouting the join as per engineer in-charge	85	Sqm	800		800.00	68000.00	700.00	59500.00	0.00
16. NS		Providing and fixing 150mm wide sheet covering over expansion joints with rawl plugs and iron screws as per design to match the colour/shade of wall treatment with 3.15mm thick aluminium fluted strips.	25	Metre	300.00		300.00	7500.00	350.00	8750.00	25.00
17. NS		Providing, laying & fixing including necessary screws 350mm wide 3.15 thick aluminium sheet bend to shape as per drawing/ instructions to act as metal cradle on expansion joint including embedding in concrete complete in all respects upto the entire satisfaction of the Engineer-in-charge.	25	Metre	650.00		650.00	16250.00	500.00	12500.00	25.00
18. NS		Providing Dr. Fixit pidiseal PS 41G (Gun grade), 42P (Pouring grade) or equivalent for horizontal and vertical expansion joint complete in all respects as per manufacturer detail to the satisfaction of EIC on all the floors.	25	Sqm.	200.00		200.00	5000.00	260.00	6500.00	10.00
19. NS		Providing and fixing 40mm CP fencing rod for palmets i/c bracket complete with all necessary fittings.as per approved engineer in-charge.	400	mtr.	100.00		100.00	40000.00	90.00	36000.00	150.00
20. NS		Providing P.O.P under ceiling i/c cost of P.O.P. scaffolding & labour as satisfaction of Engineer-in-charge.									
a)		Cornish 15cmx15cm	1000	Mtr.	25		25	25000.00	25	25000.00	1000.00
b)		Moulding 25x25cm as per design under ceiling.	800	Mtr.	15		15	12000.00	16	12800.00	800.00
c)		Flower around fan works under ceiling as per approved design.(satisfaction of engineer-in-charge)	60	Mtr.	150		150	9000.00	150	9000.00	150.00

Sr. No.	HSR NO.	Description	Qty.	Unit	Rate	C.P.	Total Rate	Estimated Cost	Qty. Likely to be Executed
PART-I: INTERNAL CIVIL WORKS (SCHEDULE ITEMS)									
	6 6	Earth work in excavation in foundation, trenches etc. in all kind of soils, not exceeding 2 mtrs. depth including dressing of bottom and sides of trenches, stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry in 15 cm layers with compaction, including disposal of all surplus soil as directed within a lead of 30 mtrs.	460	100 Cum	1100 10	350%	4935 45	22937 67	460 00
	6 27	Clearing grass and removal of the rubbish upto distance of 50m outside the periphery of the area cleared.	360	100 sqm	21 45	300%	85 60	308 88	0 00
		Dismantling brick work, tile masonry or tile lining and tile terracing							
	8 5 (b)	(b) In: cement Dismantling Concrete.	100	Cum	35 60	450%	195 60	19580 00	20 00
	8 6 (e)	(e) Reinforced cement concrete with cleaning and straightening and cutting of bars if required.	100	Cum	108 05	450%	594 28	59427 50	5 00
		Dismantling roofing							
	8 8 (g)	(G) Demolishing mud phaska in tile terracing	80	Cum	12 45	450%	68 48	5478 00	70 00
	6	Scraping							
	8 32 (a)	(a) White wash and colour wash	1000	Sqm	0 45	450%	2 48	2475 00	1000 00
	10 39	Cement concrete 1:4:8 with stone aggregate 40mm nominal size in foundation and plinth (upto 1 5m depth)							
		For Foundation	31	Cum	403 10	340%	1773 64	54982 81	41 00
	10 56	Cement concrete 1:4:8 with stone aggregate 20 mm nominal size in first storey upto 4 metres above plinth level	35	Cum	426 25	340%	1875 50	65642 50	120 00
	10 59	Cement concrete 1:2:4 with stone aggregate 20 mm nominal size in first storey upto 4 metres above plinth level	10	Cum	621 85	340%	2736 14	27361 40	30 00
	10 95 (a)	Cement concrete 1:1.5:3 with stone aggregate 20mm nominal size for reinforced concrete work in footings, strips, foundations, beams, rafts, pedestal and approach slabs of bridges etc. excluding steel reinforcement but including centering and shuttering laid in position complete in all respects (for works upto 1 5m below grounds level)	110	Cum	774 00	340%	3405 60	374616 00	118 00
	10 86 + 10 95 (a)	Cement concrete 1:1.5:3 with stone aggregate 20mm nominal size for reinforced concrete work for walls exceeding 20mm thickness (straight and curved) beams, girders, stairs, columns (square or rectangular) battens and lintels etc. excluding steel reinforcement but including centering and shuttering laid in position, complete in all respects							
	10 86 + 10 95 (a)	-do- (first storey)	80	Cum	1188 75	340%	5230 50	418440 00	78 00
	10 86 + 10 95 (a) + note(v)(b)	-do- (second storey)	145	Cum	1196 05	340%	5262 62	763079 90	83 00
	10 86 + 10 95 (a) + note(v)(b)	-do- (third storey)	5	Cum	1203 35	340%	5204 74	26473 70	5 00
	10 82 + 10 95 (a)	Cement concrete 1:1.5:3 with stone aggregate 20mm nominal size for reinforced concrete work in slab with inclination not exceeding 25 degree with horizontal, excluding steel reinforcement but including centering and shuttering laid in position complete in all respects							
	10 82 + 10 95 (a) + note(v)(b)	-do- (first storey)	50	Cum	1084 80	340%	4775 12	238656 00	40 00
	10 82 + 10 95 (a) + note(v)(b)	-do- (second storey)	105	Cum	1092 10	340%	4805 24	504550 20	95 00

18.22	Cold twisted deformed (ribbed/lor steel) bars for R.C.C. works where not included in the complete rate of R.C.C. including bending, binding and placing in position complete	680	Oil	917.35	350%	4126.13	2806173.00	542.00
10.132	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in pavements, roads, taxi tracks and runways, laid to required slope and camber, including consolidation, finishing, and tamping complete	25	Cum	642.4	340%	2826.56	70664.00	1.00
10.114	Damp proof course 40mm thick of cement concrete 1:2:4 using stone aggregate 20mm nominal size with 2 coats of bitumen 20/30 penetration at 1.65kg per sqm. laid hot and sanded	30	Sqm	35.05	340%	154.22	4626.60	30.00
11.2	First class brickwork laid in cement sand mortar 1:6 in foundation and plinth.	53	Cum	393.45	400%	1967.25	104264.25	20.00
11.7	First class brickwork laid in cement sand mortar 1:6 in first storey upto 4 meter above plinth level.							
	-do- (first storey)	70	Cum	414.45	400%	2072.25	145057.50	60.00
11.7+11.41 (i)	-do- (second storey)	210	Cum	422.70	400%	2113.50	443835.00	150.00
11.7+11.41 (i)	-do- (third storey)	17	Cum	430.95	400%	1939.28	17065.66	25.00
11.9	First class brickwork laid in cement sand mortar 1:4 in first storey upto 4 meter above plinth level							
	-do- (first storey)	20	cum	414.45	400%	2072.25	41445.00	0.00
11.9+11.41 (i)+11.42	-do- (second storey)	50	Cum	466.25	400%	2331.25	116562.50	20.00
11.9+11.41 (i)+11.42	-do- (third storey)	7	Cum	474.50	400%	1939.28	17065.66	0.00
11.48 (a)	11.43 cm thick brick wall laid in cement sand mortar 1:4 in superstructure in first storey							
	-do- (first storey)	80	Sqm	55.10	400%	275.50	22040.00	80.00
11.48 (a) + note (iv)(a)	-do- (second storey)	500	Sqm	56.05	400%	2802.50	148532.50	450.00
12.13+12.14	Terracing consisting of tiles 22.86x11.43x3.81cm laid over 87.50mm mud filling on a layer of 25mm mud plaster and another layer of mud mortar for laying the tiles							
	and storey	800	Sqm	53.90	400%	269.50	215600.00	702.00
13.43	Providing and embedding 100mm dia H.C.I. rain water without ears I.S.I mark pipe in cement mortar during masonry work.							
	100mm diameter pipe	50	Mtr	93.35	350%	420.08	21003.75	0.00
13.46 (a)	Extra over rate of item No.13.43 and 13.45 (a) in case lead joints are used instead of cement joints							
	100 mm diameter pipe	125	Each	21.30	350%	109.35	13668.75	0.00
13.50	Providing & fixing CI plain bends in position with gutter etc.							
	(a) For 100mm diameter pipe	6	Each	57.45	350%	258.53	1551.15	0.00
13.50	Top Khurra 0.6 m x 0.6 m for rain water pipe in 25mm thick cement concrete 1:2:4 over 50mm thick cement concrete 1:8:16	20	Each	12.30	200%	36.90	738.00	20.00
14.1-10.26	Sand filling under floor i/c laying consolidation, compaction & watering etc	150	Cum	69.30	340%	304.92	45738.00	400.00
13.64	Cement concrete 1:2:4 gola 10cmx10cm quadrant along junction of roof with parapet wall finished smooth where specially specified	170	Mtr	5.35	200%	16.05	2728.50	250.00
	Providing and lying cinder concrete in cement 1:15, 1cement and 15 cinder, on terraced roofs and 1st storey, laid to slope, including consolidating the same							
13.66	-do- (second storey)	70	Cum	216.65	200%	649.95	45496.50	0.00
14.1	Base course of floors consisting of 100mm thick cement concrete 1:8:16 and 100mm sand or stone filling	300	Sqm	36.95	340%	162.58	48774.00	560.00

a	14.4	-do- (second storey)	500	Sqm	15.65	340%	77.55	1121.30	0.00
b		-do- (third storey)	10	Sqm	15.95	340%	70.18	701.80	0.00
		conglomerate floor 25mm thick cement concrete topping 1:2:4							
		-do- (first storey)	10	Sqm	22.40	340%	98.56	985.60	30.00
	14.8	-do- (second storey)	15	Sqm	22.70	340%	99.88	1498.20	0.00
	14.3	Floating coat of 150mm thick neat cement laid in one operation to the topping	15	Sqm	3.70	340%	16.28	244.20	30.00
	15.5	12mm thick cement plaster 1:4 on wall							
a	15.5+note 1	-do- (first storey)	300	Sqm	12.70	340%	55.88	16764.00	300.00
	15.5+note 1	-do- (second storey)	1150	Sqm	12.88	340%	56.67	65172.80	1150.00
	15.5+note 1	-do- (third storey)	40	Sqm	13.06	340%	57.46	2298.56	40.00
		15mm thick cement plaster 1:4 on the rough side of single or half brick							
	15.10+note (1)	-do- (first storey)	610	Sqm	15.65	340%	68.86	42004.60	810.00
	15.10+note (1)	-do- (second storey)	1210	Sqm	15.83	340%	69.65	84278.92	1210.00
c	15.10+note (1)	-do- (third storey)	80	Sqm	16.01	340%	70.44	5635.52	390.00
	15.18	Rough cast exterior cement plaster on walls with a mixture of sand and gravel or crushed stone graded from 2.36mm to 12mm nominal size dashed over and including fresh plaster in 2 coats.							
	15.18+note (1)	-do- (first storey)	860	Sqm	35.40	340%	155.76	133953.60	0.00
b	15.18+note (1)	-do- (second storey)	850	Sqm	35.58	340%	156.55	133069.20	0.00
	15.18+note (1)	-do- (third storey)	120	Sqm	35.76	340%	157.34	18881.28	0.00
35	15.52	10 mm thick cement plaster 1:4 on underside of ceiling							
	15.52+Note (1)	-do- (first storey)	350	Sqm	12.65	340%	55.66	19481.00	40.00
b	15.52+Note (1)	-do- (second storey)	600	Sqm	12.83	340%	56.45	33871.20	40.00
	15.52+Note (1)	-do- (third storey)	40	Sqm	13.01	340%	57.24	2289.76	40.00
		20mm thick cement plaster damp proof course 1:3 with 2 coats of bitumen at 1.65 Kg. per laid hot and sanded.							
	15.77 (a)	Vertical							
		-do- (second storey)	150	Sqm	30.88	340%	135.87	20380.80	60.00
ii	15.77 (b)	Horizontal							
		-do- (second storey)	180	Sqm	29.13	340%	128.17	23070.96	80.00
37	17.38(a)	Teak wood wire gauze door and window shutters without spring housed in chowkets including chocks/cleats, iron hinges and screws etc.							
a		30mm thick	200	Sqm	376.45	250%	1317.58	263515.00	0.00
38	17.73	Providing and fixing six-levers brass 10cm mortice latch and lock, and a pair of lever handles with necessary screws, etc. complete (Indian make of reputed firm, such as Godrej or equivalent)	21	each	134.45	250%	369.74	7761.54	0.00
	17.82	Supplying and fixing hydraulic door closer I.S.I mark with necessary screws, etc. Complete.							
	(c)	I.S.I designation No III (size of door 851 mm to 1000 mm)	37	Each	216.50	250%	595.38	22029.06	37.00
	17.87	Providing and fixing 50mm thick aluminium sheet w/c cost of necessary screws, etc. complete	30	Sqm	90.55	250%	316.93	9507.75	5.00
	17.93& 17.93(c)&iv	Factory manufactured solid flush door shutters with block board core as per I.S. No. 1659-1669 bonded with water proof type phenol formaldehyde synthetic resin, hot pressed conforming to I.S. 2202 part I and II fixed in position including iron hinges, screws, chocks/cleats and stops etc (excluding the cost of any fitting other than specified above but including labour for fixing the same position).							

		... and edges lipped with commercial hard wood with laminated core.							
		25mm thick	70	Sqm	569.15	150%	1422.88	99601.25	0.00
IV		40 mm thick	140	Sqm	642.15	150%	1605.38	224752.50	0.00
42	17.94	Factory manufactured panelled door shutters of teak wood kiln-seasoned as per IS specification no 401 with 100mm wide vertical styles, 150mm wide lock rail, 200 mm wide bottom rail and 100mm wide other rails with panels of 12mm thick veneered, particle board or plywood of BVVR grade hot pressed including cost of iron hinges.							
		Panel of decorative plywood, both side teak faced.							
		35mm thick	150	Sqm	831.15	250%	2909.03	436353.75	0.00
43	18.12	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders, grills, grating frames, window guard iron doors openable of fixed staircase of parapet or any other type of railing, gates and tree guards etc. including cost of screws and welding rods or bolts and nuts complete fixed in position.	36	Qtl	1040.35	325%	4421.49	159173.55	12.00
44	18.16	Providing and fixing G.I. sheet 0.80 mm thick garage doors with 40mm x 40mm x 6mm angle iron frame with diagonal braces, 3mm thick gusset plates at the junctions, hooks at the top and 25 mm dia. pulleys & T-iron 50 mm x 50mm x 6mm guides at bottom including locking arrangements with handles and pintles, etc. complete.	2	Sqm	424.00	325%	1802.00	3604.00	0.00
45	18.20	Providing and fixing in position collapsible steel shutters with vertical channels 20 mm x 10 mm x 2mm and braced with flat iron diagonal 20 mm x 5 mm size, with top and bottom rails of T-iron 40 mm x 40 mm x 6 mm with 38 mm dia steel pulleys, complete with bolts, nuts, locking arrangements, stoppers, handles, etc. complete.	2	Sqm	305.45	325%	1298.16	2596.32	0.00
	18.30	Sif glass panes including special metal sash, putty of approved make.							
	(b)	Glass panes 4mm thick, exceeding 40 sq dm area.	150	Sqm	115.40	325%	490.45	73567.50	90.00
47		Pressed steel sheet frames (Chowkats) consisting of 2mm thick steel sheet of the specified section, including iron lugs (hold fasts) iron hinges conforming to PWD specifications, including bolts for fixing stops, locknotch, provision for receiving tower bolts, and finished with one coat of ready-mixed paint red lead non-setting primer of approved quality, fixed in position including the frame and cement concrete 1:3:6 for lugs complete.							
(a)	18.34(a)	Door and window frame of size 89 mm x 50mm with 40mm wide single rebate.	210	Mtr	71.55	325%	304.09	63858.38	160.00
	18.34(b)	Door and window frame of size 127 mm x 50mm with 40 mm wide single rebate.	600	Mtr.	76.80	325%	326.40	195840.00	640.00
	18.35	Providing and fixing M.S. angle and T-iron frame for door, window and ventilator including iron hold fast, butt hinges of I.S.I. mark fixed in position with machine screws and duly welded including all other suitable locking arrangements provided and welded with the frame and making holes and fixing glazing clips in the frame, filing the welds and finished with a coat of red lead non setting primer complete in all respects.	0.2	Quintal	1069.70	325%	4546.23	909.25	0.20
48	18.2	Applying pink primer or aluminium priming coat on wood work including preparation of surface knotting and stopping etc.	400	Sqm	3.75	125%	8.44	3375.00	400.00

		woodwork and plastered concrete surfaces to give an even shade (with first quality paint)							
	16.9	Applying priming coat with metal primer on new steel or iron work including preparation of surface with first quality paint)	150	Sqm	2.95	125%	6.64	995.63	150.00
	16.18	painting two coats e/c priming coat with ready mixed paint for metallic surfaces in all shades on new steel or iron work to give an even shade (with first quality paint)	150	Sqm	7.00	125%	15.75	2302.50	150.00
	16.52	preparation of plaster surface for oil bound distemper including sand papering the surface, applying 1 coat of linseed oil and filling with approved quality filler consisting of white lead, linseed oil, wamish and chalk milti including finishing the surface to the required finish complete	4400	Sqm	11.15	125%	25.09	110385.00	4400.00
54	16.27	Painting two coats with ready- mixed emulsion paint in all shades for interior use on bricks plaster, cement fibre-board etc.	590	Sqm	10.90	125%	24.53	14469.75	4400.00
55	16.26	Painting two coats with ready- mixed exterior paint in all shades on newly plastered or concrete surface of walls.	1230	Sqm	13.45	125%	30.26	37222.88	0.00
	16.44	Spirit polishing two coats including 2 coats of wood filler on new work.	600	Sqm	11.15	125%	25.09	15052.50	20.00
57	24.35	Providing and fixing premoulded bituminous joint filler, for expansion joints, including the cost of sealing compound and primer coat.							
	24.35(a)	(ii) 12mm wide	1000	Per mtr per cm depth	2.45	325%	10.41	10412.50	10000.00
58	10.89-10.95(a) note v(b)	Cement concrete 1:2.4 with stone aggregate 20mm nominal size for reinforced concrete work in fascias parapets and other thin vertical sections, not covered by item nos 10.82, 10.86 to 10.88 not exceeding 10cm thickness excluding steel reinforcement but including centring and shuttering laid in position, complete in all respects.							
		Second Storey	0	Cum	1716.25	340%	7551.50	0.00	3.00
		Third storey	0	Cum	1723.55	340%	7583.62	0.00	3.00
	13.91	Providing and fixing False Ceiling with 12mm thick Gypsum Board fixed on MS steel runners frame i/c cost of screws angles, cleats, rawel plungs with taping, filling with Gypsum compound and applying priming coat etc complete in all respects		Sqm	600.00	0%	600.00	0.00	820.00
60	13.90	Providing fixing PVC bend ISI mark							
	(a)	100 mm dia PVC bend FR=97.40	0	Each	97.40	0%	97.40	0.00	20.00
	16.25	Applying priming coat with cement primer in all shades on newly plastered or concrete exterior surfaces FR=4.15	0	Sqm	4.15	125%	9.34	0.00	8630.00
	13.89	Providing fixing PVC rain water pipe 6kg pressure of ISI mark in cement mortar during masonry work.							
	(a)	100 mm dia PVC pipe 6kg pressure FR=182	0	Mtr	182.00	0%	182.00	0.00	90.00
	15.15	20 mm thick cement plaster 1:4 in 2 coats work 1st storey							
		1st Storey FR=20.15	0	Sqm	20.15	340%	88.66	0.00	360.00
		IIInd storey FR=20.33	0	Sqm	20.33	340%	89.45	0.00	360.00
		IIIrd storey FR=51.00	0	Sqm	20.51	340%	90.24	0.00	220.00
	16.79 (b)	Providing two coats of exterior acrylic emulsion paint	0	Sqm	48.75	0%	48.75	0.00	940.00
	(b)	1st quality FR=48.75							

		note(i) fireproof timber other than teak, conforming to I.S. specification no. 1003 kiln seasoned) with 100mm wide vertical styles, 150mm wide lock rail, 200mm wide bottom rail & 100mm wide others rail with panelles of 15mm thick, tongued and grooved of commercial hard wood I/c the cost of iron hinges, screws, chocks/cleats, stops, nails etc. complete fixed in position (excluding the cost of any fittings other than specified above but including the labour for fixing the same in position)							
	(a)	35mm thick FR=424.15	0	Sqm.	424.15	250%	1484.53	0.00	50.00
66	HSR 17.92 (1) (-) note of 17.18	Factory-manufactured wire gauze door and window shutters of commercial hard wood such as hillock, champ, chikrassy and chaplash etc. As per HSR (i) 30 mm thick, Rs. @ 310.40 per sqm (322.25-11.85)=310.40	0	Sqm.	335.70	250%	1174.95	0.00	125.00
		(ii) 35mm thick, (347.55-11.85)= Rs. @ 335.70 per sqm	0	Sqm.	335.70	250%	1174.95	0.00	125.00
67	17.72	Cost of aluminium fittings, complete for doors & windows, such as tower bolts, handles etc. and screws for fittings (excluding sliding bolts)							
	(a)	For single leaf shutter FR=17.80	0	Sqm.	17.80	250%	62.30	0.00	310.00
	(b)	For double leaf shutter FR=27.45	0	Sqm.	27.45	250%	96.08	0.00	75.00
68	17.79 (b)	Providing & fixing helical door spring 150mm (superior quality), including necessary screw, complete							
		(b) Iron (@ Rs. 23.35 each)	0	Sqm.	23.85	250%	83.48	0.00	41.00
69	17.83 [b]	Providing and fixing sliding bolt with nuts and screws, etc. complete							
	(b)	aluminium							
	(i)	Size 300 x 16mm (@Rs. 44.15 each)	0	Each	44.15	250%	154.53	0.00	15.00
	(ii)	Size 250 x 16mm (@Rs. 40.30 each)	0	Each	40.30	250%	141.05	0.00	80.00
70	17.78 [b]	Providing & fixing 150mm hasps and staples with necessary screws, etc. complete							
		(b) aluminium (@ Rs. 10.35 each)	0	Each	10.35	250%	36.23	0.00	40.00
71	17.93(a) iii - note(i) of 17.18	Factory manufactured solid flush door shutters with block board core as per I.S type phenol formaldehyde synthetic resin hot pressed, conforming to I.S 2202 part I and II, fixed position including iron hinges, screws, chocks/cleats and stops, etc (excluding the cost of any fittings other than specified above, but including labour for fixing the same in position).							
	a) i	25 mm thick	0	Sqm	387.15	150%	967.88	0.00	85.00
	a) iii	35mm thick	0	Sqm	436.15	150%	1090.38	0.00	125.00
72	17.61+ note ii of this item	Providing and fixing 12 mm thick 150 mm wide pelmet of flat pressed single or three layers particle board (medium density) B.W.R. grade, with 25 mm dia teak wood curtain rod and brackets including fixing with 25 mm x 3 mm MS flat 10mm long and plugs (teak) etc. complete	0	Mtr.	74.80	250%	261.80	0.00	125.00
73	17.48+ note ii of this item	Providing and fixing flat pressed single or 3 layers particle board of BWR grade (medium density) in plain lingling butt jointed including wooden plugs (Teak), placed at 45 cm to 60 cm centres, complete with necessary nails (fram work shall be payable extra)							
	(b)	19 mm thick	0	Sqm	222.65	250%	779.28	0.00	295.00
74	17.88	Providing and fixing plastic laminated sheets thickness, not less than 1.5mm (conforming to I.S. specification), including cost of approved adhesive complete							
	(a)	natural finish	0	Sqm	310.40	250%	1086.40	0.00	680.00
75	14.87	Providing copper pin 7.5 cm long of 6mm diameter including the cost of mortar	0	each	3.00	340%	13.20	0.00	282.00
76	13.55	Supplying and fixing in position GI pipe class B spouts in chajjas and cantilevers							
	(d)	40 mm internal dia GI pipe	0	Mtr.	59.00	200%	177.00	0.00	5.00

—Sd—
EXECUTIVE ENGINEER
Construction Cell
NIT-Kurukshetra

- 68 -

Item No. 14.6 To Consider and Approve the Rough cost estimate for Installation 11kv Sub-Station for Additional Girls Hostel (300 capacity) at NIT-Kurukshetra.

The Institute has recently constructed the building of Additional Girls Hostel (300 capacity) at NIT-Kurukshetra. A 11 KV Sub-Station is to be installed for the supply of electricity to this building. A committee was constituted by the Director to decide the sub-station and other related issues of Additional Girls Hostel (300 capacity) at NIT-Kurukshetra. The Committee has prepared a rough cost estimate for this Sub-Station amounting to Rs.10.21 Lac to accommodate sub-station equipments and main LT panel. The estimate has been scrutinized by the Electrical Section of the Institute.

The B & WC is requested to consider & approve the rough cost estimate amounting to Rs.10.21 Lac for the Internal Electrification of 11 KV Sub-Station for this newly constructed Additional Girls Hostel (300 capacity) at NIT-Kurukshetra.

Item No.		Description of Item	Unit	Qty.	HSR Rate	CP %age	HSR+SP Rate	Amount
1	31.12 (D)	Supply and erection of sheet steel enclosures distribution boards suitable for MCBs etc on wall/existing board pedestal with rag bolts including bonding to earth -						
		(v) Distribution board 6 way (SPN)	1	Each	279.00	60%	446.40	446.40
2	31.13	Supply and erection of M.S. angle iron frame duly welded for Housing M.S. sheet & main switches etc. on it, fixed on wall by means of suitable size of rag bolts with cement concrete, duly painted with three coats of approved paint including one coat of red oxide						
		(ii) Size 40 mm x 40 mm x 6 mm	5	mtr	46.50	175%	127.88	639.38
3	31.17	Supply and erection of miniature circuit breaker/ isolator 240/415 V in the existing distribution board including making necessary connection:-						
		(a) Miniature Circuit Breakers of 9 K.A. breaking capacity						
		(ii) 6 amp to 32 amp (SP) Havell's/ Standard	6	Each	95.00	30%	123.50	741.00
		(iii) 40 amp to 63 amp. (SPN) Havell's/ Standard	1	Each	240.00	30%	312.00	312.00
4	31.18	Supply and erection of Fittings and Accessories						
		(xi) Bakelite angle/ straight button holder large size	2	Each	6.20	200%	18.60	37.20
		(xxiv) Erection only of 1 x 40 Watts or 2 x 40 Watts, 1220 mm long/1 x 20 watts or 2 x 20 Watts, 610 mm long fluorescent tube fitting directly on wall including necessary connection with 0.75 sq mm (24/0-20 mm) PVC copper flexible cable for connection the tube with the adjacent light point	2	Each	10.90	200%	32.70	65.40
		(xxvii) Making suitable size of wall niche including cement plastering of inside of niche for metal clad switches, branch distribution boards, bus bar chambers and energy meters	2	Cum	66.00	200%	198.00	396.00
5	31.20	Erection and carriage of fans						
		(i) Erection of ceiling fan complete with necessary earthing of fan and regulator including carriage from local railway station/Goods transport/PWD store to the site of work	1	Each	13.00	130%	29.90	29.90
		(iii) Erection of exhaust fan complete with necessary earthing of fan and regulator including carriage from local railway station /Goods transport /PWD store to the site of work	1	Each	25.00	130%	57.50	57.50
		(v) Making suitable hole in the wall up to 450 mm sweep exhaust fan including finishing the same and fixing of wire mesh duly fixed with Deodar wood frame of section 40 x 25 mm thick	1	Each	53.00	130%	121.90	121.90
		(vi) Pdg. And fixing required size of deodar wood frame of section 50 mm x 32 mm for fixing exhaust fan up to 450 mm sweep	1	Each	55.00	130%	126.50	126.50
6	31.21	Supply and erection of pipe for wiring purposes including bends inspection boxes etc. where necessary and painting as required:-						
		(xxi) Heavy gauge welded conduit pipe 20 mm dia 1.60 mm thickness flushed	30	mtr	16.30	175%	44.83	1344.75
		(xxx) Supply and erection of PVC pipe of 6 Kg. pressure, laid 1 meter below ground level complete, including digging, refilling of the trench with jointing etc.						
		(c) PVC pipe 65 MM dia	6	mtr	31.00	175%	85.25	511.50
7	31.22	Earthing						
		(iii) Earthing with G.I. earth plate 600 mm x 600 mm x 6 mm thick including accessories and providing masonry enclosures with cover plate having locking arrangement and watering pipe etc. (but without charcoal or coke and salt) complete as required	7	Each	453.00	180%	1268.40	8878.80
		(v) Extra for charcoal or coke and salt for G.I. plate or copper plate earth electrode	7	Each	186.00	180%	520.80	3645.60

Item No.		Description of Item	Unit	Qty.	HSR Rate	CP %age	HSR+SP Rate	Amount
		viii) Supply and laying 25mmx5mm GI strip at 0.5m below ground as strip earth electrode including soldering etc. as required.	30	mtr	16.20	180%	45.36	1360.80
8	31.25	Supply and erection of under ground cable 1 meter below ground level covered with sand and bricks including necessary connections, digging and refilling of trenches:- Cable Make-ICL/CCI/ECKO/HAVELLS/ POLYCAB						
		(xxix) 3.5x95 Sq mm (arm)	200	mtr	135.50	140%	325.20	65040.00
		(xxxii) 3.5x185 Sq mm (arm)	200	Meter	228.00	140%	547.20	109440.00
9	31.26	Supply and erection of under ground cable loose in existing pipe or trenches complete with necessary connections. Cable Make-ICL/CCI/ECKO/HAVELLS/ POLYCAB						
		(xxix) 3.5x95 Sq mm (arm)	100	Meter	121.10	140%	290.64	29064.00
		(xxxii) 3.5x185 Sq mm (arm)	100	Meter	215.40	140%	516.96	51696.00
10	31.28	Supply and erection of suitable compression type brass Cable glands for underground Cable -						
		(iv) 70 Sq mm to 95 Sqmm Cable 3 to 3.5 Core	8	Each	22.50	140%	54.00	432.00
		(v) 120 Sq mm to 185 Sqmm Cable 3 to 3.5 Core	8	Each	28.60	140%	68.64	549.12
11	31.35	Miscellaneous						
		(iii) Supply and erection of caution notice plate in three languages	4	Job	2.00	130%	4.60	18.40
		(iv) Supply and erection of shock restoration chart in glass frame	1	Job	37.50	130%	86.25	86.25
		(vii) Supply and erection of 75 mm x 75 mm x 60 mm deep M.S. box for telephone and inter-communication system including 2 pin 5 amp socket including cost of bakelite sheet	1	Each	18.00	130%	41.40	41.40
		(ix) Supply and erection of aluminum lugs heavy duty including crimping etc up to the entire satisfaction of the Engineer-in-charge of the work -						
		(i) 95 Sq mm	20	Each	5.60	130%	12.88	257.60
		(i) 185 Sq mm	30	Each	11.20	130%	25.76	772.80
		(xii) Supply & erection of cable route marker made of 50 cm long 10 mm dia M.S. Rod welded/revitted at the top with 10 cm dia 5 mm thick G.I. plate inscribed with 'cable' word on it, having a cross arm 30 cm long of the same dia welded at the bottom, in existing trench 45 cm below ground level	10	Each	17.00	130%	39.10	391.00
12	31.36	Wiring in 1.5 sq mm PVC insulated Copper conductor cable in 1.6 mm thick conduit pipe						
		(i) Fan point						
		(c) Long Point	1	Each	733.00	10%	806.30	806.30
		(ii) Light Point						
		(b) Medium Point	2	Each	433.00	10%	476.30	952.60
		(c) Long Point	3	Each	639.00	10%	702.90	2108.70
		(vii) 3 pin 5 amp. Plug point including earthing the 3 rd pin etc.						
		(a) Short Point	2	Each	283.00	10%	311.30	622.60
		(b) Medium Point	2	Each	466.00	10%	512.60	1025.20
		(viii) 3 pin 15 amp Plug point including earthing the 3 rd pin etc. with 4 sq mm size						
		(c) Long point	2	Each	970.00	10%	1067.00	2134.00
13	31.40	Supply and erection of PVC unsheathed copper conductor cable single core 1100 volts grade in pipe of suitable size excluding cost and erection of pipe						
		(i) Size 1.5 sq mm (1/1.40 mm)	20	mtr	10.20	10%	11.22	224.40
		(iii) Size 4.0 Sq mm (1/2 24 mm)	20	mtr	24.50	10%	26.95	539.00
		Total:						284916.00

ESTIMATE OF INTERNAL ELECTRIFICATION OF 11KV SUB-STATION BUILDING
FOR ADDITIONAL GIRLS HOSTEL (300 CAPACITY) AT NIT KURUKSHETRA
PART 2 - NON-SCHEDULE

Item No.	Description of Item	Unit	Qty.	Rate	Amount
	TRANSFORMER				
	Supply erection testing and commissioning of suitable rating 11/0 433KV distribution transformer indoor type oil immersed, natural cooled having following specifications confirming to IS 2026 latest.				
	Rate Supply frequency -50Hz per second				
	No. of phases - 3				
	No. of winding - 2				
	Winding connection - Primary Delta, Secondary star with fully insulated neutral brought out to secondary terminals.				
	Material of Winding - Copper wound				
	Voltage taps - OFF load taps on primary for $\pm 7.50\%$ in steps of 2.5%				
	Primary side connections- Box suitable for XLPE 11KV cable.				
	Vector group DYn 11 group.				
	Secondary side connections - Box suitable for 1 No. three phase (3.5C) LT cable.				
	Under carriage - Suitable under carriage with rollers with edges designed so as to permit sliding without damaging the floor and 2 Nos. lifting lugs.				
	Marshalling box - To facilitate connections of all protection devices like oil temp. indicator etc.				
	Fitting & Accessories - As per IS specifications, such as silica gel breather, conservator cable end box for HT & LT sides, 2 Nos. earthing terminals explosion vent drain valve, with plug including first filling of oil. Radiator thermometer Pockets, oil temperature indicator with A/T contacts etc. The transformer is to be erected on existing platform and making all incoming & outgoing connections. The job includes cost of transformer & painting of all MS parts & as per UHBVN terms including first filling of Transformer & warranty-02 years. Make-Kirloskar/NGEF/ Bharat Bijlee/GEC/Crompton Greaves				
	315 KVA IndoorTransformer	Each	1	400,000.00	400,000.00
2	Supply and erection for 11KV CT,PT, metering panel consisting of trivector meter CT 15/5 or 20/5 having accuracy class 0.5 and burden 05VA meter secure premier 5A HT as approved by UHBVN Ltd., PT with voltage ratio 11KV/110V, 3Phase having burden 10VA per phase for 3phase 4 wire system 0.5 accuracy class and conforming to relevant ISS and as per UHBVN specifications and requirements complete enclosed in 14/16G CRCA sheet enclosure including making all the necessary connections to the satisfaction of Engineer-in-charge. Testing & approval of C.T./P.T./Meter from UHBVN Ltd. is included in this scope of work without any further financial benefit. C.T.,P.T. & meter other detailed specifications as per UHBVN rules & regulations	Each set	1	60,000.00	60,000.00

ESTIMATE OF INTERNAL ELECTRIFICATION OF 11KV SUB-STATION BUILDING
FOR ADDITIONAL GIRLS HOSTEL (300 CAPACITY) AT NIT KURUKSHETRA
PART 2 - NON-SCHEDULE

A-2

Item No.	Description of Item	Unit	Qty.	Rate	Amount
	Providing & fixing MV danger notice plate 142x192mm made out of MS sheet 2mm thick with inscription in single red colour on front side as required & approved by UHBVN	Each	6	100.00	600.00
	Supply, installation, testing and commissioning of outdoor two pole 11KV HT structure as per drawing and specifications of 9m Height complete with following equipment inter connections and all hardware, consumables, welding rods etc.	Each	1	25,000.00	25,000.00
	a. 400A, 11KV, 3 Phase GO switch with GI operating rod and handle with padlocking arrangement = 1 No.				
	b. 11KV grade, IGE make, station class lightning arrester = 1set of 3 Nos.				
	c. 11KV, dropout fuse mounting complete with 50A DO fuses, 100A fuse holders etc.=1set of 3 Nos.				
	d. Insulated Operating rod for DO fuse = 1 No.				
	e. Two pole structure fabricated from using PCC pole 9m long as per IS specification and UHBVN requirements to accommodate the equipments mentioned above with two coat of red oxide primer and two coats of aluminium paint complete in all respect. The work has to be executed as per drawing and specifications. This shall include interconnection with electricity board 2 pole structure for supply of power= 1 set of 2 poles.				
	Supply, erection of GI pipe A class ISI marked 3m long to be laid in ground in vertical formation and upper portion to be fixed to the PCC pole with atleast 2 Nos. MS clamps of size 50mmx5mm flat duly painted				
	a. 4" (100mm dia)	Each	6	1,850.00	11,100.00
	SAFETY EQUIPMENTS				
	a. Supply & laying of 12mm thick and 1 mtr wide rubbermat for panel board	R mtr	6	900.00	5,400.00
	b. Supply, filling and fixing of following type of fire extinguishers in electrical room.				
	i) CO ₂ type fire extinguishers 5kg	No.	4	3,300.00	13,200.00
	ii) Dry powder type 5kg	No.	4	3,400.00	13,600.00
	iii) Sand bucket stand with 3 Nos MS Buckets Stand made of MS Angle 40x40x5mm medium grade	Set	4	850.00	3,400.00
A.	Supply & laying of HT cable 11KV XLPE 1m below ground level covered with sand and second class bricks / in existing trench as per site requirement complete with cost of sand brick etc. required as per satisfaction engineer-in-charge (Havell's / Polycab / Incab make or as approved by Engineer-in-charge).				
	b) 70sqmm 3C cable	mtr	50	650.00	32,500.00
B.	Supply and termination of HT cable 11KV XLPE jointing kit with cost of end joint heatshrink type with all accessories required (Raychem / Denson / M-real make or as approved by Engineer-in-charge)				
	a) Outdoor type for 70sqmm 3C cable	No.	2	5,000.00	10,000.00
	c) Indoor type for 70sqmm 3C cable	No.	3	5,000.00	15,000.00

ESTIMATE OF INTERNAL ELECTRIFICATION OF 11KV SUB-STATION BUILDING
FOR ADDITIONAL GIRLS HOSTEL (300 CAPACITY) AT NIT KURUKSHETRA
PART 2 - NON-SCHEDULE

A-3

Item No.	Description of Item	Unit	Qty.	Rate	Amount
	Providing and laying in position hume pipes NP-2 confirming to IS of following sizes in road crossings, with upper level 0.75m below road level, paved areas etc. including collars, joints filled with cement mortar 1:4 (1 cement : 4 coarse sand) finished neat and provided 75mm thick cement concrete 1:3:6 (1 cement coarse sand : 6 crushed stone) aggregate 20mm and compacted and finished smooth complete.				
a.	300mm dia pipe	RM	20	250.00	5,000.00
	DISTRIBUTION BOARDS				
NS	Supply of erection of metal clad switch with tag bolts on wall or existing angle board/pedestal including bonding to earth & necessary connections. Triple pole with neutral 400A, 415V 50HZ, 3Ph. HRC fuses 400A in metal clad chamber of L&T/English Electric/Siemens make				
		No.	1	10000.00	10,000.00
NS	Supply of following luminaries comprising of basic channel, holder, Instant start, flicker free electronic operation. Easy to fit snap on adjustable installer, compatible with energy saving tube light as per specification, including connecting wires, clamps screws fixing arrangement etc.				
	T5, 28 W Philips TCH 128/2005/865 light fitting including 28 W, T5 tube fixture	2	Each	600.00	1200.00
	Supplying ceiling fan 1400 mm sweep, double ball bearing with mechanical regulator including all accessories, wiring down rod of standard length etc. complete as required.	1	Each	1200.00	1200.00
NS (a)	Supplying exhaust fan 450 mm sweep 900 rpm heavy duty including louvers/ shutters all accessories wiring etc. complete as required.	1	Each	3835.00	3835.00
NS	Main Panel				
	supply, Installation, Testings, Commissioning, handling etc. of main panel fabricated with 2.0mm thick (14 gauge) CRCA sheet, Powder coated, earth grid at bottom with terminals, floor mounted, top & bottom cable entry plate of cubical panel having cable tray, busbar tray IP52 protection, Volt meter with Voltage selector switch, ammeter with Ammeter selector switch with C.T's, the panel single line diagram & general arrangements must be approved before fabrication & having following incomings/outgoings:				
1	Incomers				
	(i) 630A, 4 Pole, 35KA MCCB with rotary handle, overload & short cut release-01 No.				
	(ii) 400 A, 4 Pole, 35 KA, MCCB with rotary handle overload & short cut release -01 No.				
	(iii) 400A, 4 Pole, 415V change over switch				
2	Outgoings				
	(i) 200A, 4 Pole, 25KV AMCCB - 03 No's				

**ESTIMATE OF INTERNAL ELECTRIFICATION OF 11KV SUB-STATION BUILDING
FOR ADDITIONAL GIRLS HOSTEL (300 CAPACITY) AT NIT KURUKSHETRA
PART 2 - NON-SCHEDULE**

Item No.	Description of Item	Unit	Qty.	Rate	Amount
	(ii) 125A Pole, 25KA MCCB- 03 No's Makes of MCCB & Changeover- L&T/ Standard/ Havells's, ABB	1	Each	125000.00	125000.00
	Total of non schedule items				736035.00
	Total of schedule items				284916.00
	Total				1020951.00
				Say Rs.	1021000.00

Note:-

The contractor will be responsible for getting inspected/passed the electrical sub-station from the Chief Electrical Inspector Haryana Chandigarh and he will also make necessary payments of fees for this purpose to that office. The NIT Kurukshetra will, however, render necessary assistance to the contractor in this regard. No, extra payment will be made for this inspection/passing.

-----Sd-----
DEAN (E, EM & C)

-----Sd-----
PROF. I/C (EM)

-----Sd-----
A.E.E. (E)

-----Sd-----
DEAN (P & D)

-----Sd-----
DEAN (R & C)

Item No. 14.7 To Consider and Approve the Rough cost estimate of Civil works for Construction of room (Size-22'x16'with RCC Roof Slab) to accommodate 11 KV Sub-Station Equipments and main LT Panel for Additional Girls Hostel (300 capacity) at NIT- Kurukshetra.

The Institute has recently constructed the building of Additional Girls Hostel (300 capacity) at NIT-Kurukshetra. A 11 KV Sub-Station is to be installed for the supply of electricity to this building. A committee was constituted by the Director to decide the sub-station and other related issues of Additional Girls Hostel (300 capacity) at NIT-Kurukshetra. The Committee has decided to construct a room of Size 22'x16' to accommodate sub-station equipments and main LT panel. Accordingly a rough cost estimate has been prepared amounting to Rs. 5.35 Lac to cover the construction cost of this room. The estimate has been scrutinized by the Construction Cell of the Institute.

The B & WC is requested to consider & approve the Rough cost estimate of Civil works for Construction of room (Size-22'x16'with RCC Roof Slab) for Rs. 5.35 Lac for above cited work.

accommodate 11 KV Sub-Station Equipments and main LI Panel for Additional Girls hostel (300 capacity) at NIT- Kurukshetra.

(BASED ON HSR-1988 & LATEST SANCTIONED PREMIUM W.E.F. 01-02-2009)

Sr. No.	HSR No.	Description	Qty.	Unit	Rate (in Rs.)	C.P.	Total Rate (Rs.)	Amount (in Rs.)
SUB PART-I: INTERNAL CIVIL WORKS (SCHEDULE ITEMS)								
1	6.6	Earth work in excavation in foundation, trenches etc. in all kind of soils, not exceeding 2 mtrs. depth including dressing of bottom and sides of trenches, stacking the excavated soil, clear from the edge of excavation and subsequent filling around masonry in 15 cm layers with compaction, including disposal of all surplus soil as directed within a lead of 30 mtrs.	30	100 Cum	1108.10	350%	4986.45	1495.94
2	10.39	Cement concrete 1:4:8 with stone aggregate 40mm nominal size in foundation and plinth	11.00	Cum	403.10	340%	1773.64	19510.04
3	10.82+10.95(a)	Cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work in slabs with inclination not exceeding 25 degree with horizontal, excluding steel reinforcement, but including centring and shuttering laid in position complete in all respect.	8.50	Cum	1084.80	340%	4773.12	40571.52
4	10.86+10.95(a)	Cement concrete 1:2:4 with stone aggregate 20mm nominal size for reinforced concrete work for wall exceeding 20cm thickness (straight and curved) beams, girders, stair, columns (square or rectangular) battens and lintels etc. excluding steel reinforcement but including centring and shuttering, laid in position complete in all respects.	3.25	Cum	1188.75	340%	5230.50	16999.13
5	10.46	Cement concrete 1:8:16 with stone aggregate 40mm nominal size	28.01	Cum	324.90	340%	1429.56	40041.98
6	10.114	Damp proof course 40mm thick of cement concrete 1:2:4 using stone aggregate 20mm nominal size with 2 coats of bitumen 20/30 penetration at 1.65kg per sqm. laid hot and sanded.	8.37	Sqm	35.05	340%	154.22	1290.82
7	10.132	Cement concrete 1:2:4 with stone aggregate 20mm nominal size in pavement, roads, taxi-tracks and run ways, laid to required slope and camber, i/c consolidation, finishing and tamping complete.	15.04	Cum	642.40	340%	2826.56	14207.40
8	11.2	First class brickwork laid in cement sand mortar 1:6 in foundation and plinth.	25.50	Cum	393.45	400%	1967.25	50164.88
9	11.7	First class brickwork laid in cement sand mortar 1:6 in first storey upto 4 meter above plinth level.	33.50	Cum	414.45	400%	2072.25	69420.38
10	13.13	Terracing consisting of tiles 22.86x11.43x3.81cm laid over 87.50 mm mud filling on a layer 25mm mud plaster and another layer of mud mortar for laying the tiles, including two coats of bitumen laid hot at 1.65 Kg per sqm on top of RCC slab including grouting with cement sand mortar 1:3 and top surface to be left clean etc.	44.57	sqm	52.95	400%	264.75	11746.96
11	13.43	Providing and dembedding d100mm dia H.C.I rain water without ears I.S.I mark pipe in cement mortar during masonry work.	8.00	Each	93.35	350%	420.08	3360.60
12	13.49	Providing and fixing C.I plain bends in position with gutter etc.						
	a)	For 100mm dia	4.00	Each	57.45	350%	258.53	1034.10
13	13.50	Top Khurra 0.6x0.6m for rain water pipe in 25mm thick cement concrete 1:2:4 over 50 mm thick cement concrete 1:8:16.	4.00	Each	12.3	200%	36.90	147.60

14	13.01	Cement concrete 1:2:4 grade for even quadrant along junction of roof with parapet wall finished smooth, wherespecially specified.	38.50	Each	5.35	200%	16.05	617.93
15	14.1-10.25 Based derived rate	Sand filling under floor i/c laying consolidation, compaction & watering etc.	27.10	Cum	69.30	340%	304.92	8263.33
16	14.1	Base course of floor consisting of 100mm thick cement concrete 1:8:16 and 100mm sand or stone filling	90.10	Sqm.	36.95	340%	162.58	14648.46
17	14.3	Floating coat of 1.50mm thick neat cement laid in one operation to the topping	90.10	Sqm	3.70	340%	16.28	1466.83
18	14.10	Conglomerate floor 50mm thick cement concrete topping 1:2:4	90.10	Sqm	37.60	340%	165.44	14906.14
19	15.7	12mm thick cement plaster 1:6 on wall	192.94	Sqm	10.65	340%	46.86	9041.17
20	15.50	10mm thick cement plaster 1:4	80.81	Sqm	10.20	340%	44.88	3626.75
21	15.12	15mm thick cement plaster 1:6 on the rough side of singe or half brick	221.10	Sqm	13.10	340%	57.64	12744.20
22	16.1	Preparation of plywood surface for painting including sand papering the surface and applying with approved quality filler consisting of white lead, linseed oil, varnish and chalk mitti including finishing the surface to required finish complete (with first quality paint)	52.67	Sqm.	4.60	125%	10.35	545.13
23	16.2	Applying pink primer or aluminium priming coat on wood work including preparation of surface knotting and stopping etc. (with 1st quality paint)	52.67	Sqm.	3.75	125%	8.44	444.40
24	16.3	Applying two coats excluding priming coat with synthetic enamel paint in all shades on new woodwork or metallic or plastered or concrete surfaces to give an even shade (with first quality paint)	108.89	Sqm.	9.40	125%	21.15	2303.02
25	16.9	Applying priming coat with metal primer on new steel or iron work including preparation of surface with first quality paint)	56.32	Sqm.	3.15	125%	7.09	399.17
26	16.25	Applying priming coat with cement primer in all shades on newly plastered or concrete exterior surface	291.10	Sqm	4.15	125%	9.34	2718.15
27	16.52	Preparation of plastered surfaces for oil bound distemper including sand papering the surface, applying 1 coat of linseed oil and filling with approved quality filler consisting of white lead, linseed oil, warnish and chalk mitti including finishing the surface to the required finish complete	291.10	Sqm.	11.15	125%	25.09	7302.97
28	16.58	Distemping with washable oil bound distemper (of approved manufacture) two coats over one priming coat on new work.	291.10	Sqm.	9.10	125%	20.48	5960.27
29	16.79	Providing two coats of exterior acrylic emulsion paint						
	(b)	1st quality FR=48.75	221.60	Sqm	48.75	0%	48.75	10803.00
30	17.90 (a)- note-1 of 17.18	Factory manufactured panelled door or glazed window shutter of commercial hard wood such as hollock, champ, chikrassy and chaplash etc. (non-confireous timber other than teak conforming to I.S. specification no. 1003 kiln seasoned) with 100mm vide vertical styles, 150mm vide lock rail, 200mm vide bottom rail & 100mm vide others rail with panelles of 15mm thick, tongued and grooved of commercial hard wood i/c the cost of iron hinges, screws, chocks/cleats, stops, nails etc. complete fixed in position excluding the cost of any fittings other than specified above but including the labour for fixing the same in position						
	a)	For Glazed windows (30mm thick)	8.00	Sam	398.15	250%	1393.53	11148.20

	17.18	Shutter of wire Gauge Commercial Hard wood such as hollock, champ, chikrassy and chaplash (non-confireous timber other than teak conforming to I.S. specification no. 1003 kiln seasoned) with 100mm wide vertical styles, 150mm wide lock rail, 200mm wide bottom rail & wire gauze of 140G or 120G designation i/c the cost of iron hinges, screws, chocks/cleats, stops, nails etc. complete fixed in position excluding the cost of any fittings other than specified above but including the labour for fixing the same in position						
	(i)	30mm thick (Window shutters)	6.05	Sqm	310.40	250%	1086.40	6572.72
32	18.12	Wrought iron and mild steel (using angles, flats, square bars, tees and channels) ladders grills, grating frames, window guard iron doors openable of fixed staircase of parapet or any other type of railing, gates and tree guards etc. including cost of screws and welding rods or bolts and nuts complete fixed in position	2.00	Qtl.	1040.35	325%	4421.49	8842.98
33	18.22	Cold twisted deformed (ribbed/tor steel) bars for RCC works where not including bending, binding and placing in position complete.	12.00	Qtl.	917.05	350%	4126.73	49520.70
34	18.30	S/F glass panes including special metal sash putty of approved make						
	(b)	Glass panes 3mm thick, exceeding 40 sq.dm.area	6.40	Sqm	97.50	325%	414.38	2652.00
35	18.34	Pressed steel sheet frames (chowkhat), consisting of 2mm thick steel sheet of the specified section, including iron lugs (hold fasts), iron hinges, conforming to P.W.D. specifications including bolts for fixing stops, lock notch provision for receiving tower bolts and finished with one coat of ready mixed paint red lead non-setting primer of approved quality fixed in position including the cost of cement concrete 1:3:6 for filling in the frame and cement concrete 1:3:6 for lugs complete:-						
	(c)	Size 127mm x 50mm x 40mm wide double rebate	37.19	Mtr.	76.80	325%	326.40	12138.82
36	18.18 (b)	Supplying and fixing rolling shutters of approved make M.S. Laths interlocked together through their entire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets side guides 27.5cm long wire spring gauge no.2 and arrangement for inside and outside locking with push and pull operation complete including top cover 0.80mm thick (payment is to be made for the exact size of opening where rolling shutter is to be fixed);						
		With 80mm x 1.25mm M.S. Laths	9.01	Sqm	401.75	325%	1707.44	15384.01
		Total:						509464.30
		Add 5 % Contingency & misc. charges						25473.22
		Grand Total						534937.52
								Say Rs. 5.35 Lac

-----Sd-----
EXECUTIVE ENGINEER
Construction Cell
NIT-Kurukshetra